QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY	TRAFFIC CONTROL	EROSION CONTROL	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	40		40	EA	TEMPORARY LETTER OR SYMBOL (PAINT)	646.70	4
200	180		380	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	21
		45	45	SY	GEOTEXTILE UNDER STONE FILL	649.31	6
		500	500	SY	GEOTEXTILE FOR SILT FENCE	649.51	50
50			50	LB	SEED	651.15	4
400			400	LB	FERTILIZER	651.18	17
2			2	TON	AGRICULTURAL LIMESTONE	651.20	0.5
2			2	TON	HAY MULCH	651.25	0.5
10			10	CY	TOPSOIL	651.35	3
		0.5	0.5	LS	EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.10	-
		20	20	HR	MONITORING EROSION PREVENTION & SEDIMENT CONTROL PLAN	652.20	-
		0.5	0.5	LU	FIELD MAINTENANCE OF EROSION PREVENTION & SEDIMENT CONTROL PLAN (NABI)	652.30	-
		1300	1300	SY	EROSION MATTING	654.10	57.8
176			176	SF	TRAFFIC SIGNS, TYPE A	675.20	0.3
100			100	LF	FLANGED CHANNEL SIGN POST (BEGIN OPTION ITEMS)	675.301	20
100			100	LF	SQUARE TUBE SIGN POST AND ANCHOR (END OPTION ITEMS)	675.341	20
200			200	LB	TUBULAR STEEL SIGN POSTS	675.33	18
2			2	EA	FOUNDATION FOR W-SHAPE STEEL POSTS, 24" DIAMETER	675.41	0
2			2	EA	FOUNDATION FOR TUBULAR STEEL POSTS	675.43	
1			1	EA	FOUNDATION FOR TUBULAR STEEL POSTS (MOD.-CONCRETE PAD)	675.43	0
30			30	EA	REMOVING SIGNS	675.50	0
6			6	EA	ERECTING SALVAGED SIGNS	675.60	0
7			7	EA	SETTING SALVAGED POSTS	675.61	0
10			10	EA	DELINEATORS WITH STEEL POSTS	676.10	2
1			1	EA	OVERHEAD TRAFFIC SIGN SUPPORT, TUBULAR BEAM	677.11	0
1			1	EA	TRAFFIC CONTROL SIGNAL SYSTEM - INTERSECTION (MOD.)	678.15	0
1			1	EA	FLASHING BEACON - GROUND MOUNTED (MOD. - ACTUATED SIGN)	678.16	0
100			100	LF	VEHICLE LOOP DETECTOR	678.22	20
4500			4500	LF	WIRED CONDUIT (2'' PVC)	678.23	
11			11	EA	PULL BOX - STANDARD	678.25	
1			1	EA	JUNCTION BOX	678.26	
60			60	LF	ELECTRICAL CONDUIT SLEEVE (6'' DIA.)	678.30	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		REVISED 06-10-05 LSW

PROJECT NAME: I-89 EXIT 12 SB OFF RAMP
PROJECT NUMBER: IM 089-2(35)

FILE NAME: 618800F40S.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
QUANTITY SHEET

PLOT DATE: 14-JUN-2005
DRAWN BY: JDA / PGJ
CHECKED BY: EPD
SHEET 49 OF 76