STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) lb/ft FOUND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	REFRAMED SIGN	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
M.M. 84.39 RT	VERMONT 2A	1	36	36	9.0				2																		2						REMOVE SEE NOTES ON SHEET 6.		E-136B
STA. 0+00.00 RT	RAMP TRAFFIC STOPPED AHEAD	1	48	48	16.0						2												2	X	14-3 13-6	108.3# 102.6#						ATTACH 2 FLASHING BEACONS TO TOP OF SIGN	6	E-106
STA. 0+00.00 RT	WHEN FLASHING	1	48	20	6.7																											S4-4 SEE SIGN DETAIL NOTE	6	E-153
STA. 16+00.00 LT	WRONG WAY	1	36	24	6.0						1	12-0		X																		R5-1A		E-143
STA. 16+00.00 RT	WRONG WAY	1	36	24	6.0						1	12-6		X																		R5-1A		E-143
STA. 17+00.00 LT	ONLY	1	48	60	20.0																										+	R3-5L ATTACHED TO OVERHEAD		E-144
STA. 17+00.00 LT		1	48	60	20.0																											R3-6 ATTACHED TO OVERHEAD		E-144
STA. 17+00.00 LT	ONLY	1	48	60	20.0																											R3-5R ATTACHED TO OVERHEAD		E-144
STA. 18+27.45 LT	← STATE POLICE	1	72	12	6.0						2	13-0 14-0		X																		REMOVE		E-123
STA. 18+27.45 LT	← WILLISTON 1	1	72	12	6.0																													E-123
STA. 18+27.45 LT	← ESSEX JCT. 4	1	72	12	6.0																													E-123
STA. 18+27.45 LT	WRONG WAY	1	36	24	6.0																											R5-1A		E-143
STA. 18+27.45 RT	HINESBURG 8 →	1	72	12	6.0						2	12-6 13-6		X																		5 REMOVE		E-123
STA. 18+27.45 RT	BRISTOL 25 →	1	72	12	6.0																													E-123
STA. 18+27.45 RT	WRONG WAY	1	36	24	6.0																											R5-1A		E-143
NOTE 15+62 LT		1	18	18	2.25						1	9.5																							
TOTALS SHEET 1			SF ~~145.7~~ 147.95	SF	EA.	SF						FT ~~60~~ 87.0			FT					LB			EA. 2		LB ~~200~~ 210.90		EA. 2	EA.	LB					
												FT	FT	FT ~~60~~	FT	FT	FT		EA	LB	LB	LB		LB ~~200~~	LB	LB	LB							

SIGNS ON SIGN BRIDGE AT STATION 17+00.00 SHALL BE FABRICATED ON ASTM TYPE IX SILVER SHEETING WITH BLACK SYMBOLS AND TEXT. ALL OTHER GROUND MOUNTED SIGNS SHALL BE ASTM TYPE III.

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: I-89 EXIT 12 SB OFF RAMP
PROJECT NUMBER: IM 089-2(35)

FILE NAME: I8800F4TS02.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
SIGN SUMMARY SHEET

PLOT DATE: 17-MAY-2005
DRAWN BY: JDA / PGJ
CHECKED BY: EPD
SHEET 50 OF 76