COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

RICH. - SO. BURL. IM 089-2(39)			SO. BURLINGTON - COLCHESTER IM 089-3(60)				QUANTITIES	UNIT	ITEMS	ITEM NO.	ROUNDING
FULL CE	BRIDGE	ROADWAY	FULL CE	TRAINING	BRIDGE	ROADWAY	GRAND TOTAL				
		2					2	EA	THINNING AND TRIMMING FOR SIGNS	201.31	-
		3200				325	3525	CY	COMMON EXCAVATION	203.15	-
						2	2	CY	SOLID ROCK EXCAVATION	203.16	-
		325				210	535	CY	EARTH BORROW	203.30	-
		1600					1600	CY	GRANULAR BORROW	203.32	-
		13900				12500	26400	LF	SHOULDER BERM REMOVAL	203.40	-
		775					775	CY	TRENCH EXCAVATION OF EARTH	204.20	-
		1				1	2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
		197000				245400	442400	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-
		77000				85700	162700	LF	MILLED RUMBLE STRIPS	213.10	-
		725				60	785	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	-
		1900				1750	3650	TON	AGGREGATE SHOULDERS, RAP	402.13	-
		830				1145	1975	CWT	EMULSIFIED ASPHALT	404.65	-
		0.5				0.5	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
		32300				35850	68150	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30	-
		0.5				0.5	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
		0.5				0.5	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
		0.5				0.5	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
		0.5				0.5	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
		1					1	CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	-
280					665		945	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	-
100					100		200	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	-
						100	100	LF	18" CPEP	601.0915	-
		64					64	LF	24" CPEP (SL)	601.2620	-
		490					490	LF	30" CPEP (SL)	601.2625	-
						10	10	LF	CLEANING CULV. PIPE, IN PLACE (0-24 IN., INCL)	601.995	-
						1	1	EA	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-
		6				32	38	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
		40					40	LF	6 INCH UNDERDRAIN PIPE	605.10	-
		25					25	LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	-
		150				500	650	HR	POWER GRADER RENTAL	608.15	-
		120				400	520	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	-
		90				200	290	HR	POWER BROOM RENTAL, TYPE I	608.30	-
		10				100	110	HR	POWER BROOM RENTAL, TYPE II	608.31	-
		240				800	1040	HR	TRUCK RENTAL	608.37	-
		130				500	630	HR	LOADER RENTAL, TYPE I	608.40	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: SO. BURLINGTON - COLCHESTER
RICHMOND - SO. BURLINGTON

PROJECT NUMBER: IM 089-3(60)/IM 089-2(39)

FILE NAME: p05a012.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p05a012cqsl.i

PLOT DATE: $$$$$$$DATE$$$
DRAWN BY: JAR/SBJ
CHECKED BY: EPD
SHEET 3 OF 91