COMPOSITE QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

RICH. SO. BURL. IM 089-2(39)			SO. BURLINGTON - COLCHESTER IM 089-3(60)				QUANTITIES			ITEM	
FULL CE	BRIDGE	ROADWAY	FULL CE	TRAINING	BRIDGE	ROADWAY	GRAND TOTAL	UNIT	ITEMS	NO.	ROUNDING
		44				196	240	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
						100	100	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	-
		3500				4181	7681	EA	LINE STRIPING TARGETS	646.76	-
		1510					1510	SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	-
		1750				590	2340	SY	GEOTEXTILE UNDER STONE FILL	649.31	-
		3515					3515	SY	GEOTEXTILE FOR SILT FENCE	649.51	-
		220				90	310	LB	SEED	651.15	-
		915				675	1590	LB	FERTILIZER	651.18	-
		1				3	4	TON	AGRICULTURAL LIMESTONE	651.20	-
		3				3	6	TON	HAY MULCH	651.25	-
		905				790	1695	CY	TOPSOIL	651.35	-
		1					1	LS	EPSC PLAN	652.10	-
		100					100	HR	MONITORING EPSC PLAN	652.20	-
		1					1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-
		2110				2890	5000	SY	TEMPORARY EROSION MATTING	653.20	-
		65					65	CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	-
		4					4	EA	INLET PROTECTION DEVICE, TYPE I	653.40	-
		2225					2225	LF	PROJECT DEMARCATION FENCE	653.55	-
		68				825	893	SF	TRAFFIC SIGN, TYPE A	675.20	-
						235	235	SF	TRAFFIC SIGN, TYPE B	675.21	-
									BEGIN OPTION ITEMS		
		210				2000	2210	LF	FLANGED CHANNEL SIGN POST	675.301	-
		210				2000	2210	LF	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	-
									END OPTION ITEMS		
						3225	3225	LB	TUBULAR STEEL SIGN POST	675.33	-
						28	28	EA	FOUNDATION FOR TUBULAR STEEL SIGN POST	675.43	-
		14				151	165	EA	REMOVING SIGNS	675.50	-
		190				668	858	EA	DELINEATOR WITH STEEL POST	676.10	-
		165				668	833	EA	REMOVAL OF EXISTING DELINEATOR	676.12	-
		4000					4000	LF	ELECTRICAL CONDUIT (2'') (HDPE)	678.21	-
		0.5				0.5	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
		105				33	138	EA	SPECIAL PROVISION (CABLE GUARDRAIL J-BOLT, GALVANIZED)	900.620	-
		3				2	5	EA	SPECIAL PROVISION (CABLE GUARDRAIL SPLICE UNIT)	900.620	-
		25				25	50	LF	SPECIAL PROVISION (REPLACEMENT OF GUARDRAIL CABLE)	900.640	-
									BEGIN ALTERNATE ITEMS		
									ALTERNATE A		
		0.75				0.25	1	LS	SPECIAL PROVISION (TRAFFIC CONTROL, CROSSOVER)	900.645	-
									ALTERNATE B		
		0.75				0.25	1	LS	SPECIAL PROVISION (TRAFFIC CONTROL, TWO LANE NB LANE SHIFT)	900.645	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: SO. BURLINGTON - COLCHESTER
RICHMOND - SO. BURLINGTON

PROJECT NUMBER: IM 089-3(60)/IM 089-2(39)

FILE NAME:	p05a012.dgn	PLOT DATE:	$$$$$$$DATE$$$
PROJECT LEADER:	EPD	DRAWN BY:	JAR/SBJ
DESIGNED BY:	JDA	CHECKED BY:	EPD
PLOT FILE:	p05a012cqs3.i	SHEET	5 OF 91