QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
									BEGIN OPTION ITEMS		
						2000	2000	LF	FLANGED CHANNEL SIGN POST	675.301	16
						2000	2000	LF	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	16
									END OPTION ITEMS		
						3225	3225	LB	TUBULAR STEEL SIGN POST	675.33	33
						28	28	EA	FOUNDATION FOR TUBULAR STEEL SIGN POST	675.43	-
						151	151	EA	REMOVING SIGNS	675.50	-
						668	668	EA	DELINEATOR WITH STEEL POST	676.10	-
						668	668	EA	REMOVAL OF EXISTING DELINEATOR	676.12	EST.
						0.5	0.5	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
						33	33	EA	SPECIAL PROVISION (CABLE GUARDRAIL J-BOLT, GALVANIZED)	900.620	-
						2	2	EA	SPECIAL PROVISION (CABLE GUARDRAIL SPLICE UNIT)	900.620	-
						25	25	LF	SPECIAL PROVISION (REPLACEMENT OF GUARDRAIL CABLE)	900.640	5
									BEGIN ALTERNATE ITEMS		
									ALTERNATE A		
						0.25	0.25	LS	SPECIAL PROVISION (TRAFFIC CONTROL, CROSSOVER)	900.645	-
									ALTERNATE B		
						0.25	0.25	LS	SPECIAL PROVISION (TRAFFIC CONTROL, TWO LANE NB LANE SHIFT)	900.645	-
									ALTERNATE C		
						0.30	0.30	LS	SPECIAL PROVISION (TRAFFIC CONTROL, SINGLE LANE NB LANE SHIFT)	900.645	-
									END ALTERNATE ITEMS		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: SO. BURLINGTON - COLCHESTER
PROJECT NUMBER: IM 089-3(60)

FILE NAME: p05a012.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p05a012qs3.i

PLOT DATE: $$$$$$$DATE$$$
DRAWN BY: JAR/SBJ
CHECKED BY: EPD
SHEET 14 OF 91