STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET #2

BEGIN STATION	END STATION	POS.	203.15 COMMON EXC.	203.30 EARTH BORROW	203.40 SHOULDER BERM REMOVAL	204.22 TRENCH EXCAV. OF EARTH	WASTE DITCH. MAT'L	301.35 SUB. DENSE GRADED CRUSHED STONE	402.13 AGG. SHOULD., RAP	604.40 CHANGE ELEV. D. I.	604.412 REHAB. D. I. CLASS I	616.35 TREATED TIMBER CURB	616.41 REMOVAL OF EXIST. CURB	621.20 STEEL BEAM G.R., GALV.	621.50 MANUF. TERMINAL SECTION, FLARED	621.60 ANCHOR FOR S.B. RAIL	621.70 G.R. APP. SECTION, GALV. TYPE I	621.71 G.R. APP. SECTION, GALV. TYPE II	621.76 REPLACE G.R. POST ASSEMB.	621.77 REPLACE G.R. BEAM UNIT	621.80 REMOVE & DISP. OF G.R.	676.10 DELINE. WITH STEEL POST	676.12 REMOV. OF EXIST. DELINE.	SPECIAL PROVISIONS 900.620 CABLE G.R. SPLICE UNIT	SPECIAL PROVISIONS 900.620 CABLE G.R. J-BOLT GALV.	SPECIAL PROVISIONS 900.640 REPLACE G.R. CABLE	REMARKS
SOUTHBOUND			CY	CY	LF	CY	CY	CY	T	EA	EA	LF	LF	LF	EA	EA	EA	EA	EA	EA	LF	EA	EA	EA	EA	LF	
4634+25.60	4851+26.40	LT, RT		70	4000	0.5	200		550		9	100	100				1	1				109	109				SEE NOTE BELOW
4684+34	4686+59	LT																	4	5							
4684+40.5	4688+78	RT							5						1				7	5	37.5	1	1				INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 4688+40.5
4704+97	4727+45	LT							5					252	1	1			32	25	62.5	2	2				REPLACE TEXAS TWIST W/ G.R. AND ANCHOR, LENGTHEN GUARDRAIL AND INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 4727+07.5
4722+13	4727+45	RT							5					402	1	1			2	2	62.5	2	2				REPLACE TEXAS TWIST W/ STEEL BEAM G.R. & ANCHOR, INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 4727+07.5
4731+12.5	4735+75	LT																							4		REPAIR EXISTING CABLE GUARDRAIL.
4742+41	4746+91	LT												27		1			7	5	25	1	1				REPLACE TEXAS TWIST W/ G.R. AND ANCHOR.
4746+28.5	4746+91	RT												52		1					175	1	1				ATTACH TO EXISTING GUARDRAIL.
4757+15	4761+02.5	RT							5					300	1						175	1	1				INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 4760+65.
4757+15	4766+35	LT																	14	10							
4765+72.5	4766+35	RT												14.5		1					100	1	1				ATTACH TO EXISTING GUARDRAIL.
4768+01	4769+38.5	LT																	2	4							
4768+01	4773+01	RT							5					412.5	1						150	1	1				ATTACH TO EXISTING APPROACH RAIL. INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 4772+63.5.
4773+62.5	4776+00	LT												27		1		1	3	2	37.5	1	1				REPLACE TEXAS TWIST W/ G.R. AND ANCHOR. INSTALL NEW G.R. APPROACH SECTION, ATTACH TO BR.#72S BRIDGE RAIL.
4775+37.5	4776+00	RT												52		1					100	1	1				ATTACH TO EXISTING APPROACH RAIL.
4777+83	4783+12.5	RT												442							125						ATTACH TO EXISTING APPROACH RAIL.
4777+83	4783+12.5	LT																	8	2							
4784+90	4789+90	RT							5					412.5	1						175	1	1				INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 4789+52.5
4784+90	4790+40	LT							5						1				10	20	37.5	1	1				INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 4790+02.5
4824+22.5	4829+10	LT												477		1					475	1	1				REPLACE TEXAS TWIST W/ G.R. AND ANCHOR, REPLACE EXISTING GUARDRAIL.
4828+47.5	4829+10	RT												14.5		1					150	1	1				
4830+80	4835+80	RT							5					412.5	1						150	1	1				ATTACH TO BR.#74S APPROACH RAIL. INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 4835+42.5.
4830+80	4836+55	LT							5						1				9	12	87.5	1	1				ATTACH TO BR.#74S APPROACH RAIL. INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 4836+17.5.
	SUBTOTAL			70	4000	0.5	200		595		9	100	100	3297.5	9	9	1	2	98	92	2125	127	127		4		

NOTE:
ESTIMATED QUANTITIES TO BE USED AS DIRECTED BY THE RESIDENT ENGINEER. SEE PAVING PROJECT LAYOUT SHEET FOR CONSTRUCTION NOTES RELATED TO PAY ITEMS 604.40 AND 604.412.

ITEM DETAIL SUMMARY SHEET #2

PROJECT NAME: SO BURLINGTON - COLCHESTER
PROJECT NUMBER: IM 089-3(60)

FILE NAME: p05a012.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p05a012idss2.i

PLOT DATE: $$$$$$$DATE$$$
DRAWN BY: JAR/SJB
CHECKED BY: EPD
SHEET 16 OF 91