STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	STOP SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																									
NORTHBOUND & SOUTHBOUND U-TURNS		16	36	36	144.00						32			X 448′		X																	R3-4		E-143
NORTHBOUND & SOUTHBOUND MILEMARKERS	MILE 88	8	12	36	24.00						8	X 78′			X																	DI0-2 MILEMARKER SIGNS 88, 89, 90 AND 91 ARE TO BE REPLACED FOR BOTH NORTHBOUND AND SOUTHBOUND.		E-139
EXIT 13 RAMP C		10	24	30	50.00						10			X 140′		X																	W1-8R USE FLUORESCENT YELLOW SHEETING TYPE IX SEE STANDARD E-126 FOR PLACEMENT LOCATION		E-150
STA. 1+45 LT EXIT 13 RAMP C		1	18	18	2.25						1	X 8′			X																	OM1-1		E-150
STA. 1+64 LT EXIT 13 RAMP C	EXIT 13	1	72	60		30.00					2												2	182.4 X											
STA. 8+51 RT EXIT 13 RAMP C		1	36	36	9.00						2			X 28′		X																	W4-6R	43	
EXIT 13 RAMP D		7	24	30	35.00						7			X 98′		X																	W1-8R USE FLUORESCENT YELLOW SHEETING TYPE IX SEE STANDARD E-126 FOR PLACEMENT LOCATION		E-150
STA. 19+04 RT EXIT 13 RAMP D		1	30	30	6.25						1			X 14′		X																	R3-2		E-143
STA. 1+94 LT EXIT 14 RAMP A	PROHIBITED REGULATING STOPPING FOR MOTORS VEHICLES BICYCLES FARM MACHINERY SNOW VEHICLES	1	36	36	9.00						2			X 32′		X																	VR-046		E-142
	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00																													VR-002		E-142
												FT ~~93~~ 86	FT	FT ~~810~~ 760	FT ~~93~~	FT ~~810~~	FT		EA	LB	LB	LB		LB ~~228~~ 182.4	LB	LB	LB								
TOTALS		SF 288.50	SF 30.00	EA.	SF							FT ~~903~~ 846			FT ~~903~~					LB			EA. 2	LB ~~228~~ 182.4				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC & SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 1

PROJECT NAME: SO. BURLINGTON - COLCHESTER
PROJECT NUMBER: IM 089-3(60)

FILE NAME: p05a012.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p05a012tsss1.i

PLOT DATE: $$$$$$$DATE$$$
DRAWN BY: JAR/SJB
CHECKED BY: EPD
SHEET 20 OF 91