



TYPICAL SECTION
I 89 SOUTHBOUND - MM 43.950 - 48.250

NOTES:

1. ALL NECESSARY SURFACE PREPARATION (POTHOLE REPAIR, RAVELING, CRACK FILLING) SHALL BE PERFORMED PRIOR TO CONSTRUCTING THE PAVER PLACED SURFACE TREATMENT AND/OR THE QUICK SET SLURRY. ESTIMATED QUANTITIES OF ITEMS 406.25 (MOD.) AND 417.10 HAVE BEEN INCLUDED TO COVER THIS PROVISION.
2. THE PAVER PLACED SURFACE TREATMENT DETAILED ON THIS SHEET AND THE QUICK SET SLURRY DETAILED ON SHEET # 3, ALL EXISTING PAVEMENT MARKINGS SHALL BE REMOVED PRIOR TO APPLYING THE APPLICABLE TREATMENT. AN ESTIMATED QUANTITY OF 50 % REMOVAL OF EXISTING MARKINGS HAS BEEN INCLUDED TO COVER THIS PROVISION.
3. A 50' COLD PLANED WEDGE SHALL BE CONSTRUCTED AT THE PROJECT BEGIN, PROJECT END, INTERCHANGE RAMPS, AND AT ALL BEGIN/END BRIDGE APPROACHES WITHIN THE PROJECT LIMITS. THE LONGITUDINAL EDGES OF THE SURFACE TREATMENTS SHALL BE FEATHERED AS DIRECTED BY THE RESIDENT ENGINEER.

BRIDGES WITHIN THE PROJECT ARE:

BRIDGE NUMBER	36S	MM 46.920 (NO WORK REQUIRED)
BRIDGE NUMBER	37S	MM 50.000 (NO WORK REQUIRED)
BRIDGE NUMBER	38S	MM 50.290 (NO WORK REQUIRED)

REVISED 8-2-06

N.T.S.

**TYPICAL SECTION -
PAVER PLACED
SURFACE TREATMENT**

PROJECT NAME:	WILLIAMSTOWN-MONTPELIER
PROJECT NUMBER:	IM SURF(2)
FILE NAME:	/pave/05a388/p05a388.dgn
PROJECT LEADER:	WOOLAVER
DESIGNED BY:	KAS
p05a388+typ1.l	
PLOT DATE:	24-OCT-2007 13:3
DRAWN BY:	KAS
CHECKED BY:	KML
SHEET	2 OF 7