



NOTES:

1. THE SINGLE PAVEMENT LIFT WEARING COURSE SHALL BE TYPE III, ITEM 406.25, AS SHOWN ON THE TYPICALS, UNLESS DIRECTED BY THE RESIDENT ENGINEER. ALL LIQUID ASPHALT USED FOR BITUMINOUS CONCRETE PAVEMENT SHALL BE PG 58-34.
2. EMULSIFIED ASPHALT SHALL BE APPLIED ON ALL COLD PLANED SURFACES AT THE RATE OF 0.025 GAL./S.Y. OR AS DIRECTED BY THE RESIDENT ENGINEER.
3. COLD PLANING SHALL BE COMPLETED ACCORDING TO TYPICAL OR AS DIRECTED BY THE RESIDENT ENGINEER.

CHANGE TO TYPE IV

REVISED 8-2-06

**TYPICAL SECTION -
 QUICK SET SLURRY,
 TYPE II**

PROJECT NAME: WILLIAMSTOWN-MONTPELIER
 PROJECT NUMBER: IM SURF(2)

FILE NAME: /pave/05a388/p05a388.dgn PLOT DATE: 24-OCT-2007 13:3
 PROJECT LEADER: WOOLAVER DRAWN BY: KAS
 DESIGNED BY: KAS CHECKED BY: KML
 p05a388+yp2.i SHEET 3 OF 7

N.T.S.