QUANTITIES

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
36,500		36,500	SY	COLD PLANING-BIT. PAVEMENT	210.10	439
110		110	CWT	EMULSIFIED ASPHALT	404.65	7
2,500		2,500	TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25	26
10		10	TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-34) (MOD.)	406.25	EST.
75,000		75,000	SY	PAVER PLACED SURFACE TREATMENT, TYPE C	407.01	
300		300	TON	QUICK SET SLURRY, TYPE II	407.02	14
2,500		2,500	LB	BITUMINOUS CRACK FILLING	417.10	EST.
550		550	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
1,100		1,100	HR	FLAGGERS	630.15	EST.
	1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	
1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
1		1	LS	TRAFFIC CONTROL	641.10	
4		4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
56,500		56,500	LF	6 '' WHITE LINE	646.214	
45,000		45,000	LF	6 '' YELLOW LINE	646.215	
1,500		1,500	LF	12 '' WHITE LINE	646.24	
4,250		4,250	EA	LINE STRIPING TARGETS	646.76	EST.
25,250		25,250	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.
1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING-BIT. PAVEMENT
156	SY	BEGIN PROJECT
34,496	SY	END PROJECT, MM 48.25 - MM 52.45, TRAVEL LANE
876	SY	BRIDGE APPROACHES
533	SY	RAMPS
36,061	SY	SUBTOTAL
439	SY	ROUNDING
36,500	SY	TOTAL
		PAVER-PLACED SURFACE TREATMENT
70,635	SY	MAINLINE, MM 43.95 - MM 48.25
3,500	SY	INTERCHANGE 6 RAMPS
74,135	SY	SUBTOTAL
865	SY	ROUNDING
75,000	SY	TOTAL
		QUICK SET SLURRY (TYPE II)
286	TON	MAINLINE, MM 48.25 - MM 52.45, PASSING LANE
286	TON	SUBTOTAL
14	TON	ROUNDING
300	TON	TOTAL
		BITUMINOUS CONCRETE PAVEMENT (PG 58-34)
2,224	TON	MAINLINE, MM 48.25 - MM 52.45, TRAVEL LANE
250	TON	INTERCHANGE 7 RAMPS
2,474	TON	SUBTOTAL
26	TON	ROUNDING
2,500	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

REVISED 8-2-06

PROJECT NAME: WILLIAMSTOWN-MONTPELIER
PROJECT NUMBER: IM SURF(2)

FILE NAME: /pave/05a388/p05a388.dgn
PROJECT LEADER: WOOLAVER
DESIGNED BY: KAS
p05a388qs.i

PLOT DATE: 24-OCT-2007 13:3
DRAWN BY: KAS
CHECKED BY: KML
SHEET 4 OF 7