STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES

FULL E&C	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
	100	100	CY	AGGREGATE SHOULDERS, TRUCK MEASUREMENT	402.11	
	1630	1630	LF	CABLE GUARDRAIL (MOD. - BRIFEN WRSF SOCKETED POST)	621.17	
	2	2	EA	MANUFACTURED TERMINAL SECTION (MOD. - BRIFEN WRGT)	621.505	
	80	80	HR	UNIFORMED TRAFFIC OFFICERS	630.10	
	160	160	HR	FLAGGERS	630.15	
1		1	LS	TESTING EQUIPMENT - CONCRETE	631.16	
	1	1	LS	MOBILIZATION / DEMOBILIZATION	635.11	
	1	1	LS	TRAFFIC CONTROL	641.10	
	30	30	DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17	
	247	247	CY	SUPPLEMENTAL AGREEMENT (MOD) 900.508 EARTH BORROW	(203.30)	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		THIS ITEM ADDED VIA CO #01 TO CONTRUCT INLET GUARD RAIL END FLARE HAVING A 1ON 4 SIDE SLOPE
		THE MODIFICATION IS THAT THE EARTH BORROW SHALL INCLUDE TOPSOIL LIME SEED, FERTILIZER AND HAY MULCH NEEDED TO COMPLETE THE END FLARE.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT : STATEWIDE

PROJECT NO. : STP GARD(1)

DESIGN FILE NAME:
IPARM FILE NAME: brifenasl.i
SURVEYED BY:
PROJECT LEADER: MARIO DUPIGNY-GIROUX

PLOT DATE: 30-JAN-2006
SURVEY DATE:
DRAWN BY: BRM
SHEET: 3 OF 9