QUANTITIES

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

FULL C.E.	ROADWAY		QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	89 000		89 000	SY	COLD PLANING-BIT. PAVEMENT	210.10	185
	210		210	CWT	EMULSIFIED ASPHALT	404.65	4
	6 200		6 200	TON	BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	406.25	46
	1		1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
	300		300	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
	600		600	HR	FLAGGERS	630.15	EST.
1			1	LS	TESTING EQUIPMENT--BITUMINOUS	631.17	
	1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
	1		1	LS	TRAFFIC CONTROL	641.10	
	2		2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
	77 000		77 000	LF	6'' WHITE LINE (22 MIL)	646.214	308
	77 000		77 000	LF	TEMPORARY 6'' WHITE LINE (PAINT)	646.614	308
	1 250		1 250	EA	LINE STRIPING TARGETS	646.76	23
	1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		BITUMINOUS CONCRETE PAVEMENT (PG 58-34)
1 668	TON	MM 62.35 ~ 65.50 (I-91 NB)
900	TON	MM 66.70 ~ 68.40 (I-91 NB)
1 589	TON	MM 105.00 ~ 108.00 (I-91 NB)
487	TON	MM 112.03 ~ 112.95 (I-91 NB)
265	TON	MM 115.50 ~ 116.00 (I-91 NB)
636	TON	MM 116.65 ~ 117.85 (I-91 NB)
503	TON	MM 71.05 ~ 72.00 (I-91 SB)
106	TON	MM 76.30 ~ 76.50 (I-91 SB)
6 154	TON	SUBTOTAL
46	TON	ROUND
6 200	TON	TOTAL
		COLD PLANING
24 024	SY	MM 62.35 ~ 65.50 (I-91 NB)
12 965	SY	MM 66.70 ~ 68.40 (I-91 NB)
22 880	SY	MM 105.00 ~ 108.00 (I-91 NB)
7 017	SY	MM 112.03 ~ 112.95 (I-91 NB)
3 813	SY	MM 115.50 ~ 116.00 (I-91 NB)
9 152	SY	MM 116.65 ~ 117.85 (I-91 NB)
7 245	SY	MM 71.05 ~ 72.00 (I-91 SB)
1 525	SY	MM 76.30 ~ 76.50 (I-91 SB)
88 621	SY	SUBTOTAL
379	SY	ROUND
89 000	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: STATEWIDE
PROJECT NUMBER: IM RUTF(12)

FILE NAME: /pave/05k270/pk270.dgn
PROJECT LEADER: WOOLAVER
DESIGNED BY: JLR
/pave/05k270/pk270q01.i

PLOT DATE: 03-JUN-2013
DRAWN BY: JLR
CHECKED BY: JLR
SHEET 3 OF 7