

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				
							ROADWAY	TRAINING	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND
							1600				1600		CY	EARTH BORROW	203.30	40
							28800				28800		LF	SHOULDER BERM REMOVAL	203.40	50
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
							425000				425000		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	110
							152000				152000		LF	MILLED RUMBLE STRIPS	213.10	130
							60				60		CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	-
							7900				7900		TON	AGGREGATE SHOULDERS, RAP	402.13	85
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
							49500				49500		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	135
							1				1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
							1				1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
							1				1		LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
							1				1		LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
									440		440		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	10
									50		50		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.
							150				150		LF	12" CSP .064 (2-2/3 X 1/2)	601.0005	10
							13				13		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
							3				3		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
							250				250		HR	POWER GRADER RENTAL	608.15	EST.
							200				200		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
							410				410		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
							400				400		HR	TRUCK RENTAL	608.37	EST.
							100				100		HR	LOADER RENTAL, TYPE I	608.40	EST.
							2600				2600		CY	STONE FILL, TYPE I	613.10	1.5
							1200				1200		LF	BITUMINOUS CONCRETE CURB, TYPE A	616.305	15
							2650				2650		LF	REMOVAL OF EXISTING CURB	616.41	34.5
							280				280		EACH	YIELDING MARKER POSTS	619.17	EST.
							120				120		LF	CHAIN-LINK FENCE, 6 FEET	620.12	10
							6				6		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21	-
							12500				12500		LF	CABLE GUARDRAIL	621.17	196
							480				480		EACH	CABLE GUARDRAIL J-BOLT, GALVANIZED	621.173	EST.
							10				10		EACH	CABLE GUARDRAIL SPLICE UNIT	621.174	EST.
							2000				2000		LF	REPLACEMENT OF GUARDRAIL CABLE	621.175	EST.
							10750				10750		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	25
							1200				1200		EACH	STEEL BEAM GUARDRAIL DELINEATOR	621.218	30
							28				28		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
							25				25		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-
							7				7		EACH	ANCHOR FOR CABLE RAIL	621.65	-
							2				2		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	-
							1				1		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE II	621.71	-

DETAILED SUMMARY OF QUANTITIES		
QUANTITY	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
398307	SY	1-9I SB
8360	SY	PARKING AREA
6207	SY	INTERCHANGE 18
12016	SY	INTERCHANGE 19
424890	SY	SUBTOTAL
110	SY	ROUNDING
425000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
34762	TON	1-9I SB, TYPE IVS, WEARING COURSE
11617	TON	1-9I SB, TYPE IVS, LEVELING COURSE
731	TON	PARKING AREA, TYPE IVS, WEARING COURSE
244	TON	PARKING AREA, TYPE IVS, LEVELING COURSE
543	TON	INTERCHANGE 18, TYPE IVS, WEARING COURSE
181	TON	INTERCHANGE 18, TYPE IVS, LEVELING COURSE
1037	TON	INTERCHANGE 19, TYPE IVS, WEARING COURSE
226	TON	INTERCHANGE 19, TYPE IVS, LEVELING COURSE
15	TON	1-9I SB, TYPE IVS BENEATH BITUMINOUS CURB
9	TON	1-9I SB, TYPE IIS CAPPED DI'S
49365	TON	SUBTOTAL
135	TON	ROUNDING
49500	TON	TOTAL
		PROJECT NAME: NEWBURY-ST. JOHNSBURY
		PROJECT NUMBER: AC IM 091-2(76)
		FILE NAME: 06a046
		PROJECT LEADER: PTS
		DESIGNED BY: NULL
		IPARM FILE NAME: 06A046_07
		PLOT DATE: 29-JUL-2014 16:46
		DRAWN BY: JLS
		CHECKED BY: PTS
		SHEET 7 OF 33