COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

IM 089-1(22)				IM 089-1(52)				SUMMARY OF ESTIMATED QUANTITIES				
BRIDGE	EMPLOYEE TRAINEESHIP	FULL C.E.	ROADWAY	BRIDGE	EMPLOYEE TRAINEESHIP	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
-	-	-	1	-	-	-	-	1	EA	THINNING AND TRIMMING FOR SIGNS	201.31	-
-	-	-	650	-	-	-	250	900	CY	EARTH BORROW	203.30	-
-	-	-	13,400	-	-	-	12,000	25,400	LF	SHOULDER BERM REMOVAL	203.40	EST.
-	-	-	0.5	-	-	-	0.5	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
-	-	-	355,000	-	-	-	234,000	589,000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-
-	-	-	129,000	-	-	-	90,000	219,000	LF	MILLED RUMBLE STRIPS	213.10	-
-	-	-	500	-	-	-	350	850	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	-
-	-	-	2075	-	-	-	1525	3600	TON	AGGREGATE SHOULDERS, RAP	402.13	-
-	-	-	1400	-	-	-	1000	2400	CWT	EMULSIFIED ASPHALT	404.65	-
-	-	-	0.5	-	-	-	0.5	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
-	-	-	45,000	-	-	-	29,550	74,550	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30	-
-	-	-	0.5	-	-	-	0.5	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
-	-	-	0.5	-	-	-	0.5	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
-	-	-	0.5	-	-	-	0.5	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
-	-	-	0.5	-	-	-	0.5	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
80	-	-	-	-	-	-	-	80	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	-
25	-	-	-	-	-	-	-	25	CF	RAPID SETTING CONCRETE REPAIR MATERIAL W/COARSE AGGREGATE	580.20	EST.
-	-	-	22	-	-	-	27	49	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS 1	604.412	-
-	-	-	330	-	-	-	250	580	HR	POWER GRADER RENTAL	608.15	EST.
-	-	-	75	-	-	-	50	125	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
-	-	-	110	-	-	-	100	210	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
-	-	-	110	-	-	-	75	185	HR	TRUCK RENTAL	608.37	EST.
-	-	-	10	-	-	-	10	20	CY	STONE FILL, TYPE I	613.10	EST.
-	-	-	-	-	-	-	500	500	LF	TREATED TIMBER CURB	616.35	-
-	-	-	3	-	-	-	3	6	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	-
-	-	-	100	-	-	-	125	225	EA	YIELDING MARKER POSTS	619.17	EST.
-	-	-	3500	-	-	-	2100	5600	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-
-	-	-	41	-	-	-	22	63	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
-	-	-	6	-	-	-	2	8	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
-	-	-	80	-	-	-	100	180	EA	REPLACE GUARDRAIL POST ASSEMBLY	621.76	-
-	-	-	250	-	-	-	300	550	EA	REPLACE GUARDRAIL BEAM UNIT	621.77	-
-	-	-	2950	-	-	-	2900	5850	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
-	-	-	1250	-	-	-	1000	2250	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
-	-	-	2000	-	-	-	1500	3500	HR	FLAGGERS	630.15	EST.
-	-	0.5	-	-	-	0.5	-	1	LS	FIELD OFFICE, ENGINEERS	631.10	-
-	-	0.5	-	-	-	0.5	-	1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
-	-	0.5	-	-	-	0.5	-	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
-	-	0.5	-	-	-	0.5	-	1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		REFER TO SHEETS 17 AND 18 AND 29 AND 30 FOR DETAILED QUANTITY INFORMATION

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

PROJECT NAME: BETHEL - RANDOLPH & RANDOLPH - BROOKFIELD
PROJECT NUMBER: IM 089-1(52) & IM 089-1(22)

FILE NAME: p99a200.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06A048cqs1.i

PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 5 OF 61

FILE NAME = $FILE$
DATE/TIME = $DATE$
USER = $NTUSER$