COMPOSITE QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

IM 089-1(22)				IM 089-1(52)				SUMMARY OF ESTIMATED QUANTITIES				
BRIDGE	EMPLOYEE TRAINEESHIP	FULL C.E.	ROADWAY	BRIDGE	EMPLOYEE TRAINEESHIP	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
-	520	-	-	-	-	-	-	520	HR	EMPLOYEE TRAINEESHIP	634.10	-
-	-	-	0.5	-	-	-	0.5	1	LS	MOBILIZATION / DEMOBILIZATION	635.11	-
-	-	-	0.5	-	-	-	0.5	1	LS	TRAFFIC CONTROL	641.10	-
-	-	-	4	-	-	-	2	6	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
-	-	-	1125	-	-	-	-	1125	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	-
-	-	-	100,000	-	-	-	68,000	168,000	LF	DURABLE 6 INCH WHITE LINE, RECESSED	646.426	-
-	-	-	77,000	-	-	-	54,000	131,000	LF	DURABLE 6 INCH YELLOW LINE, RECESSED	646.436	-
-	-	-	5700	-	-	-	1150	6850	LF	DURABLE 12 INCH WHITE LINE, RECESSED	646.466	-
-	-	-	70	-	-	-	-	70	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	-
-	-	-	52	-	-	-	1	53	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
-	-	-	2250	-	-	-	-	2250	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	-
-	-	-	200,000	-	-	-	136,000	336,000	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	-
-	-	-	154,000	-	-	-	107,500	261,500	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	-
-	-	-	9700	-	-	-	1800	11,500	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	-
-	-	-	140	-	-	-	-	140	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	-
-	-	-	104	-	-	-	2	106	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
-	-	-	6000	-	-	-	4500	10,500	EA	LINE STRIPING TARGETS	646.76	EST.
-	-	-	25	-	-	-	25	50	SY	GEOTEXTILE UNDER STONE FILL	649.31	EST.
-	-	-	50	-	-	-	50	100	LB	SEED	651.15	EST.
-	-	-	400	-	-	-	400	800	LB	FERTILIZER	651.18	EST.
-	-	-	1	-	-	-	1	2	TON	AGRICULTURAL LIMESTONE	651.20	EST.
-	-	-	1	-	-	-	1	2	TON	HAY MULCH	651.25	EST.
-	-	-	50	-	-	-	50	100	CY	TOPSOIL	651.35	EST.
-	-	-	50	-	-	-	50	100	SY	TEMPORARY EROSION MATTING	653.20	EST.
-	-	-	890	-	-	-	297	1187	SF	TRAFFIC SIGNS, TYPE A	675.20	-
-	-	-	849	-	-	-	144	993	SF	TRAFFIC SIGNS, TYPE B	675.21	-
-	-	-	875	-	-	-	300	1175	LF	FLANGED CHANNEL SIGN POST	675.301	-
										BEGIN SIGN POST OPTION ITEMS		
-	-	-	900	-	-	-	275	1175	LF	FLANGED CHANNEL SIGN POST	675.301	-
-	-	-	900	-	-	-	275	1175	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-
										END SIGN POST OPTION ITEMS		
-	-	-	-	-	-	-	410	410	LB	W-SHAPE STEEL SIGN POST	675.31	-
-	-	-	4925	-	-	-	750	5675	LB	TUBULAR STEEL SIGN POST	675.33	-
-	-	-	-	-	-	-	2	2	EA	FOUNDATION FOR W-SHAPE STEEL POST, 24 INCH DIAMETER	675.41	-
-	-	-	48	-	-	-	6	54	EA	FOUNDATION FOR TUBULAR STEEL SIGN POST	675.43	-
-	-	-	161	-	-	-	35	196	EA	REMOVING SIGNS	675.50	-
-	-	-	5	-	-	-	-	5	EA	ERECTING SALVAGED SIGNS	675.60	-
-	-	-	441	-	-	-	448	889	EA	DELINEATOR WITH STEEL POST	676.10	-
-	-	-	450	-	-	-	450	900	EA	REMOVAL OF EXISTING DELINEATOR	676.12	EST.
-	-	-	0.5	-	-	-	0.5	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BETHEL - RANDOLPH & RANDOLPH - BROOKFIELD
PROJECT NUMBER: IM 089-1(52) & IM 089-1(22)

FILE NAME: p99a200.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06A048cqs2.i

PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 6 OF 61

FILE NAME = $FILE$
DATE/TIME = $DATE$
USER = $NTUSER$