STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
PARKING AREA: PII+28.0, RT	PROHIBITED OVERNIGHT CAMPING UNATTENDED VEHICLES COMMERCIAL ENTERPRISES 9/21/07	I	30	24	5.00						I			7/10/07 X 14-0		X		X																SIGN ID CODE VR-032		E-144
PII+39.0, LT	9/21/07	I	48	48	16.00						2			X 2@16-0																				SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS SIGN ID CODE W4-1		E-150
PI3+75.0, RT	9/21/07	I	24	30	5.00						I			7/10/07 X 14-0		X		X																	7	
	SEAT BELTS REQUIRED	I	24	18	3.00																														7	
PI4+98.0, RT	7/10/07	I	30	30	6.25						I		7/10/07 X 14-0			X		X																SIGN ID CODE R3-2		E-143
												NON-OPTION ITEMS																							
	TOTAL THIS SHEET				35.25	-						-	-	~~28.0~~	32.0	-							-	-	-					-	-	-				
	TOTAL SHEET 23				35.16	-						-	-	~~84.0~~	71.0	-							-	-	-					-	-	-				
	TOTAL SHEET 24				96.66	144.00						-	-	~~28.0~~	29.0	-							-	-	-					2	-	~~404.1~~ 908.25				
	TOTAL SHEET 25				~~19.83~~ ~~37.83~~	-						-	-	~~84.0~~	14.0	-							-	-	-					-	-	-				
	TOTAL SHEET 26				91.13	-						-	-	~~56.0~~	51.0	-							~~6~~ 3	735.9 599.25	-					-	-	-				
	TOTAL SHEET 46																														2		1088.43		FROM SHEET 46 OF 61 (22) PROJECT		
	SUBTOTAL				~~296.03~~ 278.03	144.00						-	-	~~280.0~~ 197.0	-	-							~~6~~ 3	735.9 599.25	-					-	-	~~404.1~~ 1996.68				
	ROUNDING				0.97	-						-	-	~~20.0~~	-	-							-	14.1 0.05	-					~~2~~ 4	-	~~5.9~~ 0.02				
												OPTION ITEMS																							
	TOTAL THIS SHEET				-	-						-	14.0	28.0	-	~~42.0~~							-	-	-					-	-	-				
	TOTAL SHEET 23				-	-						~~17.0~~	~~28.0~~	~~42.0~~	29.0	~~70.0~~							-	-	-					-	-	-				
	TOTAL SHEET 24				-	-						~~16.0~~	~~28.0~~	~~28.0~~	~~18.0~~	~~56.0~~							-	-	-					-	-	-				
	TOTAL SHEET 25				-	-						~~0~~	~~28.0~~	~~42.0~~	~~58.0~~	~~70.0~~							-	-	-					-	-	-				
	TOTAL SHEET 26				-	-						-	-	~~14.0~~	~~10.5~~	~~14.0~~							-	-	-					-	-	-				
	SUBTOTAL				-	-						~~47.0~~	~~98.0~~	~~154.0~~	~~143.5~~	~~252.0~~							-	-	-					-	-	-				
	ROUNDING				-	-						-	~~12.0~~	~~11.0~~	-	~~23.0~~							-	-	-					-	-	-				
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB									
												-	~~110~~ 47.0	~~165~~ (300)	~~143.5~~ (197.0)	~~275~~								~~750~~ 599.3												
	TOTALS				SF ~~297.00~~ 278.03	SF 144.00		EA.	SF			FT ~~275~~ (300) 190.5 (197.0)			FT ~~275~~					LB			EA. ~~6~~ 3	LB ~~750~~ 599.3				EA. ~~2~~ 4	EA.	LB ~~410~~ 1996.7					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BETHEL - RANDOLPH
PROJECT NUMBER: IM 089-1(52)

FILE NAME: p06a048.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06a048ts05.i
PLOT DATE: $DATE$
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 27 OF 61

FILE NAME = $FILE$
DATE/TIME = $DATE$
USER = $NTUSER$