QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			EMPLOYEE TRAINEESHIP	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			520	-	-	-	520	HR	EMPLOYEE TRAINEESHIP	634.10	-
			-	-	-	0.5	0.5	LS	MOBILIZATION / DEMOBILIZATION	635.11	-
			-	-	-	0.5	0.5	LS	TRAFFIC CONTROL	641.10	-
			-	-	-	4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
			-	-	-	1125	1125	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	23
			-	-	-	100,000	100,000	LF	DURABLE 6 INCH WHITE LINE, RECESSED	646.426	241
			-	-	-	77,000	77,000	LF	DURABLE 6 INCH YELLOW LINE, RECESSED	646.436	100
			-	-	-	5700	5700	LF	DURABLE 12 INCH WHITE LINE, RECESSED	646.466	100
			-	-	-	70	70	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	-
			-	-	-	52	52	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
			-	-	-	2250	2250	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	46
			-	-	-	200,000	200,000	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	482
			-	-	-	154,000	154,000	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	200
			-	-	-	9700	9700	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	100
			-	-	-	140	140	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	-
			-	-	-	104	104	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.
			-	-	-	6000	6000	EA	LINE STRIPING TARGETS	646.76	EST.
			-	-	-	25	25	SY	GEOTEXTILE UNDER STONE FILL	649.31	EST.
			-	-	-	50	50	LB	SEED	651.15	EST.
			-	-	-	400	400	LB	FERTILIZER	651.18	EST.
			-	-	-	1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
			-	-	-	1	1	TON	HAY MULCH	651.25	EST.
			-	-	-	50	50	CY	TOPSOIL	651.35	EST.
			-	-	-	50	50	SY	TEMPORARY EROSION MATTING	653.20	EST.
			-	-	-	890	890	SF	TRAFFIC SIGNS, TYPE A	675.20	0.11
			-	-	-	849	849	SF	TRAFFIC SIGNS, TYPE B	675.21	-
			-	-	-	875	875	LF	FLANGED CHANNEL SIGN POST	675.301	7
									BEGIN SIGN POST OPTION ITEMS		
			-	-	-	900	900	LF	FLANGED CHANNEL SIGN POST	675.301	18
			-	-	-	900	900	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	18
									END SIGN POST OPTION ITEMS		
			-	-	-	4925	4925	LB	TUBULAR STEEL SIGN POST	675.33	40.7
			-	-	-	48	48	EA	FOUNDATION FOR TUBULAR STEEL SIGN POST	675.43	-
			-	-	-	161	161	EA	REMOVING SIGNS	675.50	-
			-	-	-	5	5	EA	ERECTING SALVAGED SIGNS	675.60	-
			-	-	-	441	441	EA	DELINEATOR WITH STEEL POST	676.10	-
			-	-	-	450	450	EA	REMOVAL OF EXISTING DELINEATOR	676.12	EST.
			-	-	-	0.5	0.5	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: RANDOLPH - BROOKFIELD
PROJECT NUMBER: IM 089-1(22)

FILE NAME: p99a200.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06A048qty2.i

PLOT DATE: $DATE$
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 30 OF 61

FILE NAME = $FILE$
DATE/TIME = $DATE$
USER = $NTUSER$