STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND / REMOVAL	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGNAGE REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																							
NORTHBOUND: 37.367,RT	10/15/07 BRIDGE 32-I-N I-89	1	6	8	0.33						1	X I-9			X			X															SIGN ID CODE VD-701		E-134
37.605,LT	9/29/07	1	36	36	9.00						2			I-15 X I-14																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS SIGN ID CODE R3-4		E-143
SOUTHBOUND: 30.719,RT	9/22/07 ONE WAY	1	36	12	3.00						2			I-12 X I-12																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS SIGN ID CODE R6-12		E-142
30.844,LT	10/02/07	1	48	48	16.00						2			I-16 X I-15.5																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS SIGN ID CODE W4-1		E-150
30.873,LT	10/02/07 BRIDGE 29 I-89	1	6	8	0.33						1	X		7/18/07 I-8	X			X															SIGN ID CODE VD-701		E-134
31.000,LT	7/10/07 MILE 3 1	1	12	36	3.00						1			II-0 X		X																	SIGN ID CODE DIO-2		E-139
31.100,LT	10/02/07 BRIDGE 29-1 I-89	1	6	8	0.33						1	X		8-0 7/18/07	X			X															SIGN ID CODE VD-701		E-134
												FT ~~42.0~~ 9.0	FT 27.0 (84.5)	FT ~~14.0~~ (84.0)	FT ~~42.0~~	FT ~~14.0~~	FT		EA	LB	LB	LB		LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."	**TOTALS**	SF 31.99	SF	EA.	SF		FT OPT ~~56.0~~ (84.0) NON 36.0 (84.5)			FT ~~56.0~~					LB		EA.	LB			EA.	EA.	LB											

FILE NAME = $FILE$
DATE/TIME = $DATE$
USER = $NTUSER$

PROJECT NAME:	RANDOLPH - BROOKFIELD
PROJECT NUMBER:	IM 089-1(22)
FILE NAME: p99a200.dgn	PLOT DATE: $DATE$
PROJECT LEADER: D.E.G.	DRAWN BY: K.A.R.
DESIGNED BY: D.W.E.	CHECKED BY: D.E.G.
IPARM FILE: p06A048sss6.i	SHEET 45 OF 61