STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND / REMOVAL	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
SOUTHBOUND: 34.663,LT	ENTERING TOWN OF RANDOLPH ORANGE CO.	1	36	30	7.50						1			12-0 X 7/18/07		X		X																7	
34.663,LT	BRIDGE 30-1-5 I-89	1	6	8	0.33						1	X		8-0 7/18/07	X			X															SIGN ID CODE VD-701		E-134
34.830,LT	REST AREA 1 MILE OPEN 7AM - 11PM 9/25/07	1	156	72		78.00					2												2 7/17/07			1-20.42 ~~273.0~~ 1-18.67	570.71 9/05/07							8	
35.000,LT	MILE 3 5 7/10/07	1	12	36	3.00						1			11-0 X		X		X															SIGN ID CODE D10-2		E-139
35.070,RT		1	36	36	~~9.00~~	KEEP EXISTING					~~2~~			~~X~~																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS SIGN ID CODE R3-4		E-143
35.105,RT		1	36	36	~~9.00~~	KEEP EXISTING					~~2~~			~~X~~																			SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS SIGN ID CODE R3-4		E-143
35.500,LT	MOOSE CROSSING 9/05/07	1	48	48	16.00						2												2 7/20/07	1-16 ~~263.0~~ 1-15	235.60								SIGN ID CODE VW-000	11	
	NEXT 5 MILES 9/05/07	1	30	24	5.00																												SIGN ID CODE W7-3a	11	
35.814,LT	BRIDGE 30-2-5 I-89 9/05/07	1	6	8	0.33						1	X		8-0 7/18/07	X			X															SIGN ID CODE VD-701		E-134
												FT ~~28.0~~	FT 39.0 —	FT ~~28.0~~ (56.0)	FT ~~28.0~~	FT ~~28.0~~	FT		EA	LB	LB	LB		LB ~~235.60~~ ~~263.0~~	LB	LB	LB ~~570.71~~ ~~273.0~~							
		TOTALS			SF ~~50.16~~ 32.16	SF 78.00	EA.	SF				OPT	FT ~~56.0~~ (56.0)	39.0 —		FT ~~56.0~~					LB			EA. 4		LB ~~536.0~~ 806.31			EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

FILE NAME = $FILE$
DATE/TIME = $DATE$
USER = $NTUSER$

PROJECT NAME: RANDOLPH - BROOKFIELD
PROJECT NUMBER: IM 089-1(22)

FILE NAME: p99a200.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06A048sss9.i

PLOT DATE: $DATE$
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 48 OF 61