STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND / REMOVAL	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 (1.88)	2.0 (2.16)	2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	4.0 (1.7)	4.0 MOD (1.7)	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 (7.6)	3.5 (9.0)	4.0 (10.8)	5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
RAMP C: C8+85.0,RT	7/06/07	1	36	36	9.00		1				2			14-0 X 15-0																				SIGN ID CODE W3-A		E-150
C10+58.0,RT	EAST / WEST	1 1	30 30	15 15	3.13 3.13						2												2 7/18/07	1-15.5 ~~189.8~~ I-13.75	222.3 9/04/07							X	SIGN ID CODE M3-4 SIGN ID CODE M3-3		E-136B E-136B
9/04/07	VERMONT 66 / VERMONT 66	1 1	36 36	36 36	9.00 9.00																												SIGN ID CODE MI-5 SIGN ID CODE MI-5		E-136B E-136B
9/04/07	← / →	1 1	21 21	15 15	2.19 2.19																												SIGN ID CODE M6-1 SIGN ID CODE M6-1		E-136B E-136B
C11+37.0,RT	RANDOLPH 3 →	1	72	12	6.00						2												2 7/18/07	1-13.67 ~~188.5~~ I-12.0	195.09 9/04/07								SIGN ID CODE DI-1		E-123
9/04/07	← VT TECHNICAL COLLEGE 1	1	72	12	6.00																												SIGN ID CODE DI-1		E-123
9/04/07	← VERMONT VETERANS MEM CEMETERY 1	1	72	20	10.00																												SIGN ID CODE DI-2		E-123
C14+00.0,RT	SERVICES → DIESEL 3 →	1 1	72 72	10 10	5.00 5.00						2												2 7/18/07	1-15.17 ~~113.4~~ I-13.33	216.6 9/04/07										11 11	
9/04/07	← 3 GAS 24 HRS HOSPITAL 3 →	1 1	72 72	10 10	5.00 5.00																														11 11	
9/04/07	← 1 CAMPING 5 → INFORMATION →	1 1	72 72	10 10	5.00 5.00																														11 11	
	WRONG WAY	1	36	24	6.00																												SIGN ID CODE R5-1A BACK-TO-BACK		E-143
C14+00.0,LT 7/10/07	WRONG WAY	1	36	24	6.00						2			14-0 X 15-0																				SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS SIGN ID CODE R5-1A		E-143
												FT	FT (58.0)	FT - ~~(56.0)~~	FT	FT	FT		EA	LB	LB	LB		LB ~~491.7~~ 633.99	LB	LB	LB							
TOTALS			SF 101.64	SF	EA. 1	SF						FT - NON ~~(56.0)~~ (58.0)			FT					LB			EA. 6	LB ~~491.7~~ 633.99				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

FILE NAME = $FILE$
DATE/TIME = $DATE$
USER = $MYUSER$

PROJECT NAME: RANDOLPH - BROOKFIELD
PROJECT NUMBER: IM 089-1(22)

FILE NAME: p99a200.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06A048sss13.i
PLOT DATE: $DATE$
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 52 OF 61