STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND / REMOVAL	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
														OPTION ITEMS																							
RAMP C: CI6+25.0,LT 7/10/07	ONE WAY / ONE WAY	2 1	36 36	12 12	3.00 3.00						1			13-0 X		X		X															SIGN ID CODE R6-IR SIGN ID CODE R6-IL BACK-TO-BACK		E-142 E-142
	STOP / DO NOT ENTER	2 1	30 30	30 30	6.25 6.25																												SIGN ID CODE RI-1 SIGN ID CODE R5-1 BACK-TO-BACK		E-143 E-143
CI6+25.0,RT 7/10/07	ONE WAY / ONE WAY	2 1	36 36	12 12	3.00 3.00						1			13-0 X		X		X															SIGN ID CODE R6-IR SIGN ID CODE R6-IL BACK-TO-BACK		E-142 E-142
	STOP / DO NOT ENTER	2 1	30 30	30 30	6.25 6.25																												SIGN ID CODE RI-1 SIGN ID CODE R5-1 BACK-TO-BACK		E-143 E-143
RAMP D: D4+00.0,RT 10/11/07	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00						2			1-17 X 1-16																			SIGNS SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS SIGN ID CODE VR-002		E-142
	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS BICYCLES MOPEDS FARM MACHINERY SNOW VEHICLES	1	36	36	9.00																												SIGN ID CODE VR-046		E-142
DI4+36.0,RT 10/11/07		1	30	30	6.25						1			X 1-14		X		X															SIGN ID CODE R3-2		E-143
NORTHBOUND REST AREA: X7+90.0, LT 9/28/07		1	18	18	2.25						1	X 1-9			X			X															SIGN ID CODE OMI-1		E-150
X7+90.0, LT 9/27/07	REST AREA WEIGH STATION	1	96	132		88.00					2												2 7/25/07			1-20.67 ~~296.4~~ 1-21.08				609.55 9/07/07				8	
TOTALS			SF 63.50	SF 88.00	EA.	SF						FT OPT ~~56.0~~ NON (~~28.0~~)	49.0 (33.0)		FT ~~56.00~~					LB			EA. 2	LB ~~296.4~~ 609.55				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC OPERATIONS SECTION "SIGN POST DESIGN GUIDELINE."

FT: ~~14.0~~ 9.0 | 40.0 (33.0) | ~~42.0~~ (~~28.0~~) | ~~14.0~~ | ~~42.0~~ | EA | LB | LB | LB | LB | LB | LB ~~296.4~~ 609.55

PROJECT NAME: RANDOLPH - BROOKFIELD
PROJECT NUMBER: IM 089-1(22)

FILE NAME: p99a200.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: D.W.E.
IPARM FILE: p06A048sss14.i
PLOT DATE: $DATE$
DRAWN BY: K.A.R.
CHECKED BY: D.E.G.
SHEET 53 OF 61

FILE NAME = $FILE$
DATE/TIME = $DATE$
USER = $NTUSER$