STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLIP SLEEVE	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) kg/m FND-ATION	75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
NORTHBOUND 111.450 NB	BRIDGE 68 I-91	1	150	250	0.04						1		4.27 X		X			X															VD-701	78	
112.000 NB	MILE 112	1	300	1200	0.36						1			4.27 X		X		X															D10-3		E-139
112.150 NB	PARKING AREA 1 MILE R	1	3600	1350		4.86					2												2		101.56 X								D5-3	72	
112.159 NB MED		1	900	900	0.81						2			8.54 X		~~X~~		~~X~~															R3-4		E-143
112.563 NB TO 128.204 NB	BRIDGE XX-N I-91	9	150	250	0.36						9		30.05 X		X			X															VD-701 NOT SHOWN ON PLANS. SEE PAGE 78 OF 88	78	
112.907 NB MED		1	900	900	0.81						2			8.54 X		~~X~~		~~X~~															R3-4		E-143
113.000 NB	MILE 113	1	300	1200	0.36						1			2.44 X		X		X															D10-3		E-139
113.095 NB	BRIDGE 69-N I-91	1	150	250	0.04						1		3.05 X		X			X															VD-701	78	
113.140 NB	PARKING AREA NEXT RIGHT R	1	3600	1350		4.86					2												2			157.06 X								72	
113.208 NB	EXIT 30 M.P.H.	1	1200	1500	1.80						2												2	98.16 X									W13-2		E-150
113.295 NB		1	450	450	0.20						1		4.27 X		~~X~~			~~X~~															OM-1		E-150
113.298 NB	PARKING AREA R	1	2250	1950		4.39					2												2		127.47 X									72	
113.400 NB		1	1200	1200	1.44						2												2	93.00 X									W4-1		E-150
113.500 MED	ONE WAY	1	900	300	0.27						2			8.53 X		~~X~~		~~X~~															R6-1R		E-142
114.000 NB	MILE 114	1	300	1200	0.36						1			4.27 X		X		X															D10-3		E-139
115.000 NB	MILE 115	1	300	1200	0.36						1			4.27 X		~~X~~		~~X~~															D10-3		E-139
116.19 NB	BRIDGE 69-9 I-91						1						2.44 X																						
												m 0.0	m ~~31.7~~ 44.08	m ~~41.0~~ 40.86	m 31.7	m ~~41.0~~	m ~~0.0~~		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg ~~180.9~~ 191.16	kg ~~210.9~~ 229.03	kg ~~140.1~~ 157.04	kg 0.0								
							1						84.94												577.23										
		SHEET TOTALS			m2 7.21	m2 14.11	EA. ~~0~~	m2 0.00				84.94 m ~~72.7~~			m ~~72.7~~					kg 0.0			EA. 10	kg ~~531.9~~				EA. 0	EA. 0	kg 0				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: RYEGATE-ST. JOHNSBURY
PROJECT NUMBER: IM 091-2(73)

FILE NAME	tsssRyegate.xls	PLOT DATE	12/12/06
PROJECT LEADER:	CRB	DRAWN BY:	JCS
DESIGNED BY:	PTS	CHECKED BY:	DAM
OLD REF. NO.:	97-0194	SHEET 39	OF 88