STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) kg/m FND-ATION	75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
SOUTHBOUND 111.460 SB	BRIDGE 68 I-91	1	150	250	0.04						1		2.44 X		X			X															VD-701	78	
112.000 SB	MILE 112	1	300	1200	0.36						1			4.27 X		X		X															D10-3		E-139
112.161 SB MED		1	900	900	0.81						2			8.53 X		X		X															R3-4		E-143
112.563 SB TO 128.204 SB	BRIDGE XX-N I-91	9	150	250	0.36						9		27.45 X		X			X															VD-701 NOT SHOWN ON PLANS.	78	
112.909 SB MED		1	900	900	0.81						2			8.53 X		X		X															R3-4		E-143
113.000 SB	MILE 113	1	300	1200	0.36						1			4.27 X		X		X															D10-3		E-139
113.145 SB	BRIDGE 69-S I-91	1	150	250	0.04						1		2.44 X		X			X															VD-701	78	
113.330 SB	EMERGENCY VEHICLE ENTRANCE	1	1200	1200	1.44																												VW-544	77	
	1500 FEET	1	600	450	0.27						2												2	98.16 X									W16-2		
114.000 SB	MILE 114	1	300	1200	0.36						1			4.27 X		X		X															D10-3		E-139
115.000 SB	MILE 115	1	300	1200	0.36						1			4.27 X		~~X~~		~~X~~															D10-3		E-139
115.295 SB MED	ONE WAY	1	900	300	0.27						2			8.53 X		~~X~~		~~X~~															R6-1R		E-142
115.400 SB		1	1200	1200	1.44						2												2	91.27 X									W4-1		E-150
115.505 SB	PARKING AREA	1	2250	1950		4.39					2												2		127.47 X									72	
115.508 SB		1	450	450	0.20						1		2.44 X		X			X															OM-1		E-150
												m 0.0	m ~~31.3~~ 32.3	m ~~41.8~~ 42.67	m 31.3	m 41.8	m 0.0		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg ~~177.5~~ 189.43	kg ~~110.2~~ 127.47	kg 0.0	kg 0.0								
												75.0												316.9											
		SHEET TOTALS			m2 7.12	m2 4.39	EA. 0	m2 0.00				m ~~73.1~~			m ~~73.1~~					kg 0.0			EA. 6	kg ~~287.7~~				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: RYEGATE-ST. JOHNSBURY
PROJECT NUMBER: IM 091-2(73)

FILE NAME	fsssRyegate.xls	PLOT DATE	12/12/06
PROJECT LEADER:	CRB	DRAWN BY:	JCS
DESIGNED BY:	PTS	CHECKED BY:	DAM
OLD REF. NO.:	97-0194	SHEET 46	OF 88