STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) 75 kg/m 1.9	100 kg/m 2.5	100MD kg/m 2.5	TUBULAR STEEL DIA (mm) FND-ATION	75 kg/m 11.3	90 kg/m 13.6	100 kg/m 16.1	125 kg/m 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
115.584 SB	RAMP 30 M.P.H.	1	1200	1500	1.80						2												2	98.16 X									W13-3		E-150
115.700 SB	PARKING AREA NEXT RIGHT	1	3600	1350		4.86					2												2			149.67 X								72	
115.702 SB MED		1	900	900	0.81						2			8.53 X		X		X															R3-4		E-143
116.000 SB	MILE 116	1	300	1200	0.36						1			4.27 X		X		X															D10-3		E-139
116.430 SB	PARKING AREA 1 MILE	1	3600	1350		4.86					2												2		103.63 X								D5-3	72	
117.000 SB	MILE 117	1	300	1200	0.36						1			4.27 X		X		X															D10-3		E-139
117.230 SB	ENTERING TOWN OF RYEGATE	1	900	600	0.54						2			9.15 X		X		X															I-2		E-131
117.942 SB MED		1	900	900	0.81						2			9.76 X		X		X															R3-4		E-143
118.000 SB	MILE 118	1	300	1200	0.36						1			3.66 X		X		X															D10-3		E-139
118.236 SB 118.33 SB	BRIDGE 70-S I-91 / BRIDGE 70-3 S I-91	1	150	250	0.04		1				1		2.44 X 2.44		X			X															VD-701	78	
119.000 SB	MILE 119	1	300	1200	0.36						1			3.66 X		X		X															D10-3		E-139
119.350 SB	KEEP RIGHT EXCEPT TO PASS	1	1200	1500	1.80						2												2	101.61 X									VR-132	77	
119.603 SB	Wells River 12 / White River Jct 50	1	3600	900		3.24					2												2		93.27 X								E-7	75	
119.802 SB MED		1	900	900	0.81						2			9.76 X		X		X															R3-4		E-143
119.860 SB	SPEED LIMIT 65	1	1200	1500	1.80																												R2-1		E-142
	MINIMUM 40	1	1200	1200	1.44						2												2	125.71 X									VR-141		E-142
116.22 SB	BRIDGE 69.9 I-91						1						2.44 X																						
												m 0.0	m 2.6 7.32	m 51.4 53.06	m 2.6	m 51.4	m 0.0	EA. 0		kg 0.0	kg 0.0	kg 0.0		kg 313.1 325.48	kg 225.0 196.9	kg 158.6 147.67	kg 0.0								
												60.38														672.05									
	SHEET TOTALS	m2 11.29	m2 12.96	EA. 2 ~~0~~	m2 ~~0.00~~							m 60.4 ~~54.0~~			m ~~54.0~~					kg 0.0			EA. 12	kg ~~696.7~~				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: RYEGATE-ST. JOHNSBURY
PROJECT NUMBER: IM 091-2(73)

FILE NAME:	fsssRyegate.xls	PLOT DATE:	12/12/06
PROJECT LEADER:	CRB	DRAWN BY:	JCS
DESIGNED BY:	PTS	CHECKED BY:	DAM
OLD REF. NO.:	97-0194	SHEET	47 OF 88