STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 22

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	FND-ATION	TUBULAR STEEL DIA (mm) kg/m 75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#18 0.207 BSH RT	← ST. JOHNSBURY 10	1	1800	300	0.54						2			9.15 X		~~X~~		~~X~~																D1-1a		E-123
0.245 BSH RT	NORTH	1	600	300	0.18		I																											M3-1 SIGN KNOCKED DOWN BY PLOWS. REINSTALLED		E-135
	INTERSTATE 91	1	600	600	0.36		I																											M1-1		E-135
	←	1	525	375	0.20		I				1			4.88 X		~~X~~		~~X~~																M6-1		E-135
0.252 BSH LT	NORTH	1	600	300	0.18																													M3-1		E-135
	INTERSTATE 91	1	600	600	0.36																													M1-1		E-135
	←	1	525	375	0.20						1			4.27 X		~~X~~		~~X~~																M6-1		E-135
0.252 BSH LT	TO	1	600	300	0.18																													M4-5		E-136A
	5	1	600	600	0.36																													M1-4		E-136A
	→	1	525	375	0.20						1			4.27 X		~~X~~		~~X~~																M6-1		E-136A
0.252 BSH LT	SOUTH	1	600	300	0.18																													M3-3		E-135
	NORTH	1	600	300	0.18																													M3-1		E-135
	INTERSTATE 91	1	600	600	0.36																													M1-1		E-135
	INTERSTATE 91	1	600	600	0.36																													M1-1		E-135
	↑	1	525	375	0.20						2			9.76 X		~~X~~		~~X~~														#2		M6-3		E-135
	→	1	525	375	0.20																													M6-1		E-135
0.275 BSH RT	TO	1	600	300	0.18																													M4-5		E-136A
	5	1	600	600	0.36																													M1-4		E-136A
	↑	1	525	375	0.20						1			4.88 X		~~X~~		~~X~~																M6-3		E-136A
												m 0.0	m 0.0	m ~~34.7~~ 37.2	m 0.0	m 34.7	m 0.0		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg 0.0	kg 0.0	kg 0.0	kg 0.0								
												37.2																								
							3																													
		SHEET TOTALS			m2 4.98	m2 0.00	EA. ~~0~~	m2 0.00				m ~~34.7~~			m ~~34.7~~					kg 0.0			EA. 0	kg 0.0				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: RYEGATE-ST. JOHNSBURY
PROJECT NUMBER: IM 091-2(73)

FILE NAME:	tsssRyegate.xls	PLOT DATE:	12/12/06
PROJECT LEADER:	CRB	DRAWN BY:	JCS
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0194	SHEET 60	OF 68