STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 24

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	FND-ATION	TUBULAR STEEL DIA (mm) kg/m 75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
SCENIC 121.76 NB																																				
0.045 RAMP A LT	WRONG WAY	1	900	600	0.54						2			8.54 X		~~X~~		~~X~~															R5-1a		E-143
0.045 RAMP A RT	WRONG WAY	1	900	600	0.54						2			8.54 X		~~X~~		~~X~~															R5-1a		E-143
121.80 NB	BRIDGE 80-2 I-91						1						2.44 X																						
0.065 RAMP A RT	PROHIBITED OVERNIGHT CAMPING UNATTENDED VEHICLES COMMERCIAL ENTERPRISES	1	750	600	0.45						1			4.27 X		~~X~~		~~X~~															VR-032		E-144
0.090 RAMP A RT	PROHIBITED	1	600	900	0.54						1			4.88 X		~~X~~		~~X~~															VR-278		E-144
0.130 RAMP A RT	ONE WAY	1	900	300	0.27						2			8.54 X		~~X~~		~~X~~															R6-1L		E-142
0.140 RAMP A RT		1	600	600	0.36						1			4.88 X		~~X~~		~~X~~															R3-2		E-143
												m 0.0	m ~~0.0~~ 2.44	m ~~34.7~~ 39.6	m 0.0	m 34.7	m 0.0		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg 0.0	kg 0.0	kg 0.0	kg 0.0								
													42.04																						
		SHEET TOTALS			m2 2.70	m2 0.00	EA. ~~0~~ 1	m2 ~~0.00~~					m ~~34.7~~			m ~~34.7~~				kg 0.0			EA. 0	kg 0.0				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: RYEGATE-ST. JOHNSBURY
PROJECT NUMBER: IM 091-2(73)

FILE NAME	fsssRyegate.xls	PLOT DATE	12/12/06
PROJECT LEADER:	CRB	DRAWN BY:	JCS
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0194	SHEET 62	OF 88