STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 25

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	~~SQUARE STEEL (mm) 44 kg/m 3.4~~	~~50 3.9~~	~~63 5.0~~	~~ANCHOR~~	~~SLEEVE~~	TUBULAR ALUMINUM DIA (mm) 75 kg/m 1.93	100 2.5	100MD 2.5	FND-ATION	TUBULAR STEEL DIA (mm) 75 kg/m 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#19 0.142 RAMP A RT	RAMP 50 M.P.H.	1	1200	1500	1.80						2												2	99.02 X									W13-3		E-150
0.210 RAMP A RT		1	1200	1200	1.44						2												2	92.13 X									W4-3		E-155
0.305 RAMP A RT		1	600	600	0.36						1			4.27 X		~~X~~		~~X~~															R3-2		E-143
0.061 RAMP B RT		1	450	450	0.20						1		2.44 X		~~X~~			~~X~~															OM-1		E-150
0.063 RAMP B RT		1	1200	1200	1.44						2												2	84.39 X									W12-1		
0.110 RAMP B RT	BRIDGE ICES BEFORE ROAD	1	1200	1200	1.44						2									19.13 X													W8-13		E-150
0.152 RAMP B RT	BRIDGE 81-B-1 I-91	1	150	250	0.04						1		2.44 X		~~X~~			~~X~~															VD-701	78	
0.465 RAMP B RT		1	600	600	0.36						1			4.27 X		~~X~~		~~X~~															R3-2		E-143
0.225 RAMP C RT		1	600	600	0.36						1			4.27 X		~~X~~		~~X~~															R3-2		E-143
0.060 RAMP D RT	RAMP 45 M.P.H.	1	1200	1500	1.80						2									22.21 X													W13-3		E-150
0.320 RAMP D RT		1	1200	1200	1.44						2									18.68 X													W4-3		E-155
0.431 RAMP D LT	ONE WAY	1	900	300	0.27						2			4.27 X		~~X~~		~~X~~															R6-1R		E-142
0.350 RT RAMP D							1				1		2.44 X																						
INT.#20 0.077 RAMP A RT	SOUTH	1	600	300	0.18																												M3-3		E-136A
	NORTH	1	600	300	0.18																												M3-1		E-136A
	5	1	600	600	0.36																												M1-4		E-136A
	5	1	600	600	0.36																												M1-4		E-136A
	←	1	525	375	0.20						2			9.75 X		~~X~~		~~X~~														#2	M6-1		E-136A
	↗	1	525	375	0.20																												M6-2		E-136A
												m 0.0	~~5.3~~ 7.32	~~31.6~~ 26.83	m 5.3	m 31.6	m 0.0		EA. 0	kg ~~70.8~~ 60.02	kg 0.0	kg 0.0		kg ~~264.6~~	kg 0.0	kg 0.0	kg 0.0							
													34.2								60.02				275.54									
SHEET TOTALS					m2 12.43	m2 0.00	EA. ~~0~~ 1	m2 ~~0.00~~				m ~~36.9~~			m ~~36.9~~					kg ~~70.8~~			EA. 6	kg 275.54 ~~264.6~~				EA. 0	EA. 0	kg 0				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: RYEGATE-ST. JOHNSBURY
PROJECT NUMBER: IM 091-2(73)

FILE NAME	fsss Ryegate.xls	PLOT DATE	12/12/06
PROJECT LEADER:	CRB	DRAWN BY:	JCS
DESIGNED BY:	PTS	CHECKED BY:	DAM
OLD REF. NO.:	97-0194	SHEET 63	OF 88