STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 26

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	~~SQUARE STEEL (mm) 44 kg/m 3.4~~	~~50 kg/m 3.9~~	~~63 kg/m 5.0~~	~~ANCHOR~~	~~SLEEVE~~	TUBULAR ALUMINUM DIA (mm) 75 kg/m 1.9	100 kg/m 2.5	100MD 2.5	FND-ATION	TUBULAR STEEL DIA (mm) 75 kg/m 11.3	90 kg/m 13.6	100 kg/m 16.1	125 kg/m 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#20 0.115 RAMP A RT	← PASSUMPSIC 2	1	1800	300	0.54																													D1-1a		E-123
	ST. JOHNSBURY 1 ↗	1	1800	300	0.54						2			8.53 X		~~X~~		~~X~~																D1-1a		E-123
0.153 RAMP A RT	SERVICES 1 ↗ / WRONG WAY	1 1	~~1800~~ 1370 900	~~250~~ 190 600	~~0.45~~ 0.26 0.54																													VD-502S BACK TO BACK R5-1a		E-133 E-143
	← LODGING ↗	1	~~1800~~ 1370	~~250~~ 190	~~0.45~~ 0.26																													VD-502L		E-133
	CAMPING 4 ↗	1	~~1800~~ 1370	~~250~~ 190	~~0.45~~ 0.26																													VD-502C		E-133
	← STATE POLICE	1	~~1800~~ 1370	~~250~~ 190	~~0.45~~ 0.26						2												2	82.66 X										VD-502SP		E-133
0.205 RAMP A LT		1	450	450	0.20						1		2.44 X		~~X~~			~~X~~																OM-1		E-150
0.205 RAMP A RT		1	900	900	0.81						1			4.88 X		~~X~~		~~X~~																W3-2a		E-150
0.207 RAMP A LT	SOUTH / NORTH	1 1	600 600	300 300	0.18 0.18																													M3-3 M3-1		E-136A E-136A
	5 / 5	1 1	600 600	600 600	0.36 0.36																													M1-4 M1-4		E-136A E-136A
	← / ↗	1 1	525 525	375 375	0.20 0.20						2			9.75 X		~~X~~		~~X~~															#2	M6-1 M6-2		E-136A E-136A
0.284 RAMP A RT	YIELD	1			0.35						1			4.88 X		~~X~~		~~X~~																R1-2 900X900X900		E-146
0.045 RAMP B RT	YIELD	1			0.35						1			4.27 X		~~X~~		~~X~~																R1-2 900X900X900		E-146
											m 0.0	m ~~2.7~~ 2.44	m ~~31.2~~ 32.31	m 2.7	m 31.2	m 0.0		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg ~~79.1~~ 82.66	kg 0.0	kg 0.0	kg 0.0								
												34.8																								
		SHEET TOTALS			5.85 ~~6.61~~	m2 0.00	EA. 0	m2 ~~0.00~~				m ~~33.9~~			m ~~33.9~~					kg 0.0			EA. 2	82.66 kg ~~79.1~~				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: RYEGATE-ST. JOHNSBURY
PROJECT NUMBER: IM 091-2(73)

FILE NAME	fsss Ryegate.xls	PLOT DATE	12/12/06
PROJECT LEADER:	CRB	DRAWN BY:	JCS
DESIGNED BY:	PTS	CHECKED BY:	DAM
OLD REF. NO.:	97-0194	SHEET 64	OF 88