STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 29

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	FND-ATION	TUBULAR STEEL DIA (mm) kg/m 75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#20 0.500 RTE 5 MED.		1	600	750	0.45																													R4-7		E-144
		1	450	450	0.20						1			4.27 X		~~X~~		~~X~~																OM-1		E-150
0.550 RTE 5 LT	PASSUMPSIC 2	1	1800	300	0.54																													D2-1		E-123
	BARNET 10	1	1800	300	0.54						2			9.54 X		~~X~~		~~X~~																D2-1		E-123
0.550 RTE 5 RT	J CT	1	525	375	0.20																													M2-1		E-135
	INTERSTATE 91	1	600	600	0.36						1			4.27 X		~~X~~		~~X~~																M1-1		E-135
0.590 RTE 5 RT TO	ST. JOHNSBURY 1	1	1800 600	300 300	0.54 0.18		I																											D1-1a		E-123
93	BARNET 9	1	1800 600	300 600	0.54 0.36		I																	III.98 X										D1-1a	C.O. #1 2 NEW T.S.S.P.	E-123
	WHITE RIVER JCT 82	1	1800 525	300 375	0.54 0.20		I				2												2	82.66 X										D1-1a		E-123
0.600 RTE 5 LT	SOUTH	1	600	300	0.18																													M3-3		E-136A
	5	1	600	600	0.36						1			4.88 X		~~X~~		~~X~~																M1-4		E-136A
0.610 RTE 5 RT	ONLY	1	1200	750	0.90						2			8.54 X		~~X~~		~~X~~																VR-927		E-145B
0.617 RTE 5 LT		1	900	900	0.81						1			4.27 X		~~X~~		~~X~~																W4-2		E-151
0.629 RTE 5 MED.		1	600	750	0.45																													R4-7		E-144
		1	450	450	0.20						1			4.27 X		~~X~~		~~X~~																OM-1		E-150
												m 0.0	m 0.0	m ~~43.7~~	m 0.0	m 43.7	m 0.0		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg ~~76.9~~	kg 0.0	kg 0.0	kg 0.0								
												40.0													194.64										
					7.55		3																													
	SHEET TOTALS				m2 ~~6.81~~	m2 0.00	EA. ~~0~~	m2 ~~0.00~~				m ~~43.7~~			m ~~43.7~~					kg 0.0			EA. 2	kg ~~76.9~~				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD.
POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: RYEGATE-ST. JOHNSBURY
PROJECT NUMBER: IM 091-2(73)

FILE NAME	tsssRyegate.xls	PLOT DATE	12/12/06
PROJECT LEADER:	CRB	DRAWN BY:	JCS
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0194	SHEET 67	OF 88