STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SILEVY	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) FND-ATION	kg/m 75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
130.039 SB	BRIDGE 85-1 I-91	1	150	250	0.04						1		2.44 X		X			X															VD-701 NOT SHOWN ON PLANS.	70	
130.110 SB		1	1200	1200	1.44																												VW-397	69	
	GROOVED SHOULDER	1	600	450	0.27						2									22.2 X													VP-396	69	
130.170 SB	BRIDGE 86 I-91	1	150	250	0.04						1		2.44 X		X			X															VD-701	70	
130.205 SB	SOUTH	1	750	375	0.28																												M3-1		E-135
	INTERSTATE 91	1	900	900	0.81																												M1-1		E-135
	EISENHOWER INTERSTATE SYSTEM	1	900	900	0.81						1												1	50.8 X									M1-10		E-135
130.252 SB MED		1	900	900	0.81						2			8.53 X		X		X															R3-4		E-143
130.300 SB	EMERGENCY STOPPING ONLY	1	1200	900	1.08						2									19.4 X													R8-7		E-142
130.410 SB MED	ONE WAY	1	900	300	0.27						2			8.53 X		X		X															R6-1R		E-142
130.510 SB		1	1200	1200	1.44						2												2	95.6 X									W4-1		E-150
130.520 SB	BRIDGE 87 I-91	1	150	250	0.04						1		2.44 X		X			X															VD-701	70	
130.600 SB	EXIT 21	1	1800	1500		2.70					2												2	86.1 X									E5-1a		E-131
130.604 SB		1	450	450	0.20						1		2.44 X		X			X															OM-1		E-150
130.675 SB	BRIDGE 88 I-91	1	150	250	0.04						1		2.44 X		X			X															VD-701	70	
130.690 SB	EXIT 30 M.P.H.	1	1200	1500	1.80						2												2	96.4 X									W13-2		E-150
												m 0.0	m ~~13.1~~ 12.2	m ~~17.2~~ 17.06	m 0.0	m 13.1	m 17.2		EA. 0	kg ~~47.0~~ 41.6	kg 0.0	kg 0.0		kg ~~314.1~~ 328.9	kg 0.0	kg 0.0	kg 0.0							
												29.26			0					41.6				328.9										
		SHEET TOTALS			m2 9.37	m2 2.70	EA. 0	m2 0.00				m ~~30.3~~			m ~~30.3~~					kg ~~47.0~~			EA. 7	kg ~~314.1~~				EA. 0	EA. 0	kg 0				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: ST. JOHNSBURY-LYNDON
PROJECT NUMBER: HES 091-3(42)

FILE NAME:	tsssSJ.xls	PLOT DATE:	1/4/2007
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0211	SHEET	37 OF 130