STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 23

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SIELVL	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) FND-ATION	kg/m 75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#21 2.300 RTE 2 RT	EXIT 30 ALP.N.	1	900	1200	1.08						2			9.76 X		X		X															W13-2		E-150
2.331 RTE 2 RT		1	450	450	0.20						1		2.44 X		X			X															OM-1		E-150
2.334 RTE 2 RT	NORTH	1	750	375	0.28																												M3-1		E-135
	INTERSTATE 91	1	900	900	0.81																												M1-1		E-135
		1	525	375	0.20						1												1	49.94 X									M6-2		E-135
2.350 RTE 2 RT	SPEED LIMIT 45	1	1200	1200	1.44						2												2	96.44 X									W3-5		
2.370 RTE 2 LT	JCT	1	525	375	0.20																												M2-1		E-135
	INTERSTATE 91	1	900	900	0.81						1									9.7 X													M1-1		E-135
INT.#22 0.082 RAMP A RT	TO	1	600	300	0.18																												M4-5		E-136A
	5	1	600	600	0.36																												M1-4		E-136A
		1	525	375	0.20						1			4.88 X		X		X															M6-1		E-136A
0.120 RAMP A RT	ST JOHNSBURY 2	1	1800	300	0.54						2			8.54 X		X		X															D1-1a		E-123
0.156 RAMP A LT	WRONG WAY	1	900	600	0.54																												R5-1a		E-143
		1	600	600	0.36						2			4.27 X		X		X															R9-4a		E-143
0.168 RAMP A RT	GAS /DIESEL → WRONG WAY	1 1	~~1800~~ 1370 1	~~250~~ 190 1	~~0.45~~ 0.26 0.54																												VD-502G BACK TO BACK R5-1a		E-133 E-143
	FOOD → LODGING →	1 1	~~1800~~ 1370 1 ~~1800~~ 1370	~~250~~ 190 1 ~~250~~ 190	~~0.45~~ 0.26 ~~0.45~~ 0.26																												VD-502F VD-502L		E-133 E-133
	INFORMATION → HOSPITAL →	1 1	~~1800~~ 1370 1 ~~1800~~ 1370	~~250~~ 190 1 ~~250~~ 190	~~0.45~~ 0.26 ~~0.45~~ 0.26						2												2	88.69 X									VD-502I VD-502H		E-133 E-133
												m 0.0	m ~~2.7~~ 2.44	m ~~31.4~~ 27.45	m 0.0	m 2.7	m 31.4		EA. 0	kg ~~9.5~~ 9.7	kg 0.0	kg 0.0		kg ~~220.4~~	kg 0.0	kg 0.0	kg 0.0								
					9.04							29.89			0									235.07											
		SHEET TOTALS			m2 ~~9.99~~	m2 0.00	EA. 0	m2 0.00				m ~~34.1~~			m ~~34.1~~					9.7 kg ~~9.5~~			EA. 5	kg ~~220.4~~				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: ST. JOHNSBURY-LYNDON
PROJECT NUMBER: HES 091-3(42)

FILE NAME:	tsssSTJ.xls	PLOT DATE:	1/4/2007
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0211	SHEET	51 OF 130