STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 25

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) 75 kg/m 1.9	100 kg/m 2.5	100MD kg/m 2.5	TUBULAR STEEL DIA (mm) FND-ATION	75 kg/m 11.3	90 kg/m 13.6	100 kg/m 16.1	125 kg/m 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#22 0.242 RAMP C LT		1	750	750	0.56																													R1-1		E-143
																																		BACK TO BACK		
		1	750	750	0.56																													R5-1		E-143
		1	900	300	0.27						1			4.67 X		X		X																R6-1L		E-142
																																		BACK TO BACK		
		1	900	300	0.27																													R6-1R		E-142
INT.#22 0.242 RAMP C RT		1	750	750	0.56																													R1-1		E-143
		1	750	750	0.56																													R5-1		E-143
		1	900	300	0.27						1			4.67 X		X		X																R6-1L		E-142
		1	900	300	0.27																													R6-1R		E-142
INT.#22 0.030 RAMP D RT		1	900	900	0.81																													VR-046		E-142
		1	900	900	0.81						2									19.97 X														VR-002		E-142
0.208 RAMP D RT		1	600	600	0.36						1			4.27 X		X		X																R3-2		E-143
INT.#22 0.700 STJSH RT		1	750	750	0.56						1			4.27 X		X		X																W11-6		
0.742 STJSH RT		1	750	750	0.56																													W11-7		
		1	600	450	0.27						2			9.76 X		X		X																W16-4		E-153
0.770 STJSH LT		1	600	750	0.45						1			4.27 X		X		X																R2-1		E-142
0.780 STJSH RT		1	900	900	0.81						1			4.27 X		X		X																W4-2		E-151
0.810 STJSH LT		1	750	750	0.56																													W7-1b		
		1	600	450	0.27						2			9.76 X		X		X																W7-2b		E-152
0.830 STJSH RT		1	525	375	0.20																													M2-1		E-135
		1	600	600	0.36						1			4.27 X		X		X																M1-1		E-135
0.845 STJSH LT		1	1800	300	0.54						2			8.54 X		X		X																D2-1		E-123
												m 0.0	m 0.0	m ~~57.7~~ 58.75	m 0.0	m 0.0	m ~~57.7~~		EA. 0	kg ~~23.2~~ 19.97	kg 0.0	kg 0.0		kg 0.0	kg 0.0	kg 0.0	kg 0.0								
														58.75			0																			
SHEET TOTALS					m2 9.88	m2 0.00	EA. 0	m2 0.00				m ~~57.7~~			m ~~57.7~~					19.97 kg ~~23.2~~			EA. 0	kg 0.0				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: ST. JOHNSBURY-LYNDON
PROJECT NUMBER: HES 091-3(42)

FILE NAME:	tsssStJ.xls	PLOT DATE:	1/4/2007
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0211	SHEET	53 OF 130