STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 26

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) kg/m FND-ATION	75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#22 0.850 STJSH RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1			4.27 X		X		X															VR-017		E-141
0.860 STJSH RT	NO OUTLET	1	750	750	0.56						1			4.27 X		X		X															W14-2		
0.865 STJSH RT	STOP / Pvt. LaPIERRE Dr	1	750	750	0.56		X				1			4.27 X		X		X															R1-1		E-143
0.880 STJSH LT	TO 5	1 1	600 600	300 600	0.18 0.36						1			4.27 X		X		X															M4-5 M1-4		E-136A E-136A
0.880 STJSH RT	WHITE RIVER JCT 62 / NEWPORT 41	1 1	1800 1800	300 300	0.54 0.54																												D1-1a D1-1a		E-123 E-123
	SOUTH / NORTH	1 1	600 600	300 300	0.18 0.18																												M3-3 M3-1		E-135 E-135
	INTERSTATE 91 / INTERSTATE 91	1 1	600 600	600 600	0.36 0.36																												M1-1 M1-1		E-135 E-135
	↑ / →	1 1	525 525	375 375	0.20 0.20						2												2	94.72 X									M6-3 M6-1		E-135 E-135
0.897 STJSH RT	TO	1	600	300	0.18																												M4-5		E-136A
	5	1	600	600	0.36																												M1-4		E-136A
	→	1	525	375	0.20						1			4.88 X		X		X															M6-1		E-136A
0.897 STJSH RT	NORTH	1	600	300	0.18																												M3-1		E-135
	INTERSTATE 91	1	600	600	0.36																												M1-1		E-135
	←	1	525	375	0.20						1			4.88 X		X		X															M6-1		E-135
0.915 STJSH LT	NORTH	1	600	300	0.18																												M3-1		E-135
	INTERSTATE 91	1	600	600	0.36																												M1-1		E-135
	←	1	525	375	0.20						1			4.27 X		X		X															M6-1		E-135
												m 0.0	m 0.0	m ~~30.7~~ 31.11	m 0.0	m 0.0	m ~~30.7~~		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg ~~101.7~~ 94.72	kg 0.0	kg 0.0	kg 0.0							
												31.11			0									94.72										
	SHEET TOTALS		m2 6.89	m2 0.00	EA. 1	m2 0.00						m ~~30.7~~			m ~~30.7~~					kg 0.0			EA. 2	kg ~~101.7~~				EA. 0	EA. 0	kg 0				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: ST. JOHNSBURY-LYNDON
PROJECT NUMBER: HES 091-3(42)

FILE NAME:	tsssSTJ.xls	PLOT DATE:	1/4/2007
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0211	SHEET	54 OF 130