STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 28

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) kg/m FND-ATION	75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#23 0.036 RAMP A RT		1			0.35						1			4.27 X		X		X															R1-2 900X900X900		E-146
0.030 RAMP A RT		1	750	750	0.56																												W1-11		
		1	450	450	0.20						1												1	39.61 X									W13-1		E-155
0.060 RAMP A RT		1	900	900	0.81																												VR-046		E-142
		1	900	900	0.81						2												2	91.27 X									VR-002		E-142
0.068 -0.180 LT RAMP A		10	450	600	2.70						10			42.7 X 8.54		X		X															W1-8 TWO EACH KNOCKED DOWN DURING WINTER		E-150
0.200 RAMP A RT		1	600	600	0.36						1			4.27 X		X		X															R3-2		E-143
INT.#23 0.100 RAMP B RT		1	900	900	0.81						1			4.27 X		X		X															W3-1a		E-150
0.139 RAMP B RT	NORTH SOUTH	1	600	300	0.18																												M3-1		E-136A
		1	600	300	0.18																												M3-3		E-136A
	5 5	1	600	600	0.36																												M1-4		E-136A
		1	600	600	0.36																												M1-4		E-136A
		1	525	375	0.20						2			9.75 X		X		X														#2	M6-1		E-136A
		1	525	375	0.20																												M6-1		E-136A
0.177 RAMP B RT	← LYNDONVILLE 2	1	1800	300	0.54																												D1-1a		E-123
	← LYNDON STATE COLLEGE 3	1	1800	300	0.54																												D1-1a		E-123
	LYNDON 1 →	1	1800	300	0.54						2												2	79.22 X									D1-1a		E-123
EXIT 21 0.081 RAMP A	STOP AHEAD	1	900	900	0.81						2			9.76 X																			ADDED SIGN		
												m 0.0	m 0.0	m ~~61.3~~ 83.56	m 0.0	m 0.0	m 61.3		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg ~~212.6~~ 210.1	kg 0.0	kg 0.0	kg 0.0							
												83.56												210.1										
SHEET TOTALS					10.51 m2 ~~9.70~~	m2 0.00	EA. 0	m2 ~~0.00~~				m ~~61.3~~			m ~~61.3~~					kg 0.0			EA. 5	kg ~~212.6~~			EA. 0	EA. 0	kg 0				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: ST. JOHNSBURY-LYNDON
PROJECT NUMBER: HES 091-3(42)

FILE NAME	tsssSJ.xls	PLOT DATE	1/4/2007
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0211	SHEET	56 OF 130