STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	~~SQUARE STEEL (mm) 44 kg/m 3.4~~	~~60 kg/m 3.9~~	~~63 kg/m 5.0~~	~~ANCHOR~~	~~SILVI~~	TUBULAR ALUMINUM DIA (mm) 75 kg/m 1.9	100 kg/m 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) FND-ATION	75 kg/m 11.3	90 kg/m 13.6	100 kg/m 16.1	125 kg/m 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
1.204 NB		1	450	450	0.20						1		2.44 X		X			X																OM-1		E-150
1.205 NB		1	1950	1950		3.80					2												2	96 X											E-131
1.257 NB		1	1200	1200	1.44						2												2	81 X									W4-1		E-150
1.355 NB MED		1	900	300	0.27						2			8.534 X		X		X															R6-1R		E-142
1.407 NB TO 9.621 NB		6	150	250	0.24						6		14.64 X		X			X															VD-701 NOT SHOWN ON PLANS.	121	
1.543 NB		1	150	250	0.04						1		2.44 X		X			X															VD-701	121	
2.000 NB		1	300	600	0.18						1			3.05 X		X		X															D10-1		E-139
2.683 NB		1	1800	1200		2.16					2												2	89 X											E-131
3.000 NB		1	300	600	0.18						1			3.05 X		X		X															D10-1		E-139
3.228 NB MED		1	900	900	0.81						2			8.534 X		X		X															R3-4		E-143
4.000 NB		1	300	600	0.18						1			3.05 X		X		X															D10-1		E-139
4.582 NB		1	150	250	0.04						1		2.44 X		X			X															VD-701	121	
4.624 NB		1	1200	1200	1.44																													120	
		1	600	450	0.27						2												2	92 X									W16-2		
5.000 NB		1	300	600	0.18						1			3.05 X		X		X															D10-1		E-139
5.450 NB MED		1	900	900	0.81						2			8.534 X		X		X															R3-4		E-143
																							~~2~~												
												m 0.0	m ~~23.5~~ 21.96	m ~~41.4~~ 37.79	m 0.0	m 23.5	m 41.4		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg 386.2	kg 0.0	kg 0.0	kg 0.0								
												59.8											8		358										
		SHEET TOTALS			m2 6.28	m2 5.96	EA. 0	m2 0.00				m ~~64.9~~			m ~~64.9~~					kg 0.0			EA. ~~10~~	kg ~~386.2~~				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERFORD
PROJECT NUMBER: HES 093-1(10)

FILE NAME:	tsssWaterford.xls	PLOT DATE:	1/4/2007
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0211	SHEET	97 OF 130