STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	~~SQUARE STEEL (mm) kg/m 44 3.4~~	~~60 3.9~~	~~63 5.0~~	~~ANCHOR~~	~~SIELV~~	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) kg/m FND-ATION	75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
7.364 NB	EXIT 1	1	1800	1500		2.70					2												2	90 X									E5-1a		E-131
7.510 NB	BRIDGE 6 I-93	1	150	250	0.04						1		2.44 X		X			X															VD-701	121	
7.593 NB		1	1200	1200	1.44						2									19.707 X													W4-1		E-150
7.690 NB MED	ONE WAY	1	900	300	0.27						2			8.534 X		X		X															R6-1R		E-142
7.874 NB MED		1	900	900	0.81						2			8.534 X		X		X															R3-4		E-143
7.927 NB	EMERGENCY STOPPING ONLY	1	1200	900	1.08						2												2	84 X									R8-7		E-142
8.000 NB	NORTH	1	750	375	0.28																												M3-1		E-135
	INTERSTATE 93	1	900	900	0.81																												M1-1		E-135
	EISENHOWER INTERSTATE SYSTEM	1	900	900	0.81						1												1	50 X									M1-10 POST WAS TOO SHORT CHANGED TO CORRECT LENGTH POST		E-135
8.000 NB	MILE 8	1	300	600	0.18						1			3.05 X		X		X															D10-1		E-139
8.098 NB		1	1200	1200	1.44																												VW-397	120	
	GROOVED SHOULDER	1	600	450	0.27						2									21.471 X													VP-396	120	
8.188 NB	SPEED LIMIT 65	1	1200	1500	1.80																												R2-1		E-142
	MINIMUM 40	1	1200	1200	1.44						2												2	119 X									VR-141		E-142
8.316 NB	St. Johnsbury 5 White River Jct 62	1	3600	900		3.24					2												2			150 X							E7	117	
8.670 NB	KEEP RIGHT EXCEPT TO PASS	1	1200	1500	1.80						2												2	99 X									VR-132	120	
8.710 NB	BRIDGE 7-N I-93	1	150	250	0.04						1		2.44 X		X			X															VD-701	121	
												m 0.0	m ~~5.2~~ 4.88	m ~~20.5~~ 20.11	m 0.0	m 5.2	m 20.5		EA. 0	kg 46.7	kg 0.0	kg 0.0		kg ~~434.1~~ 442	kg 0.0	kg ~~161.9~~ 150	kg 0.0								
												25.0								41.2				592											
		SHEET TOTALS			m2 12.51	m2 5.94	EA. 0	m2 0.00				m ~~25.7~~			m ~~25.7~~					kg ~~46.7~~			EA. 11	kg ~~596.0~~				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERFORD
PROJECT NUMBER: HES 093-1(10)

FILE NAME:	tsssWaterford.xls	PLOT DATE:	1/4/2007
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0211	SHEET	99 OF 130