STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SIELV	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) FND-ATION	kg/m 75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#1 7.270 RTE 18 LT	SOUTH	1	600	300	0.18																													M3-3		E136-B
	VERMONT 18	1	600	600	0.36						1			4.267 X		X		X																M1-5		E-136B
7.289 RTE 18 RT	NORTH	1	600	300	0.18																													M3-1		E-135
	NORTH	1	600	300	0.18																													M3-1		E136-B
	SOUTH	1	600	300	0.18																													M3-3		E-135
	INTERSTATE 93	1	600	600	0.36																													M1-1		E-135
	VERMONT 18	1	600	600	0.36																													M1-5		E-136B
	INTERSTATE 93	1	600	600	0.36																													M1-1		E-135
	↑	1	525	375	0.20																													M6-3		E-135
	↑	1	525	375	0.20						2												2	79 X								#3		M6-3		E136-B
	→	1	525	375	0.20																													M6-1		E-135
7.293 RTE 18 RT	NORTH	1	600	300	0.18																													M3-1		E136-B
	TO	1	600	300	0.18																													M4-5		E-136A
	SOUTH	1	600	300	0.18																													M3-3		E136-B
	VERMONT 18	1	600	600	0.36																													M1-5		E-136B
	2	1	600	600	0.36																													M1-4		E-136A
	VERMONT 18	1	600	600	0.36																													M1-5		E-136B
	←	1	525	375	0.20																													M6-1		E136-B
	←	1	525	375	0.20						2												2	77 X								#3		M6-1		E-136A
	→	1	525	375	0.20																													M6-1		E136-B
7.293 RTE 18 RT	SOUTH	1	600	300	0.18																													M3-3		E-135
	INTERSTATE 93	1	600	600	0.36																													M1-1		E-135
	←	1	525	375	0.20						1			4.877 X		X		X																M6-1		E-135
7.311 RTE 18 RT	TRUCK ROUTE 2 WEST NEXT LEFT	1	3000	2400		7.20					2												2				239 X								119	
7.315 RTE 18 LT	← LITTLETON NH 14	1	1800	300	0.54																													D1-1a		E-123
	SOUTH	1	600	300	0.18																													M3-1		E-135
	INTERSTATE 93	1	600	600	0.36																													M1-1		E-135
	←	1	525	375	0.20						2									19.707 X														M6-1		E-135
												m 0.0	m 0.0	m 8.7	m 0.0	m 0.0	m 8.7		EA. 0	kg 22.7	kg 0.0	kg 0.0		kg ~~165.0~~ 156	kg 0.0	kg 0.0	kg ~~239.8~~ 239								
												9.2								19.7				395												
		SHEET TOTALS			m2 7.00	m2 7.20	EA. 0	m2 ~~0.00~~				m ~~8.7~~			m ~~8.7~~					kg ~~22.7~~			EA. 6	kg ~~404.8~~				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERFORD
PROJECT NUMBER: HES 093-1(10)

FILE NAME:	tsssWaterford.xls	PLOT DATE:	1/4/2007
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0211	SHEET	110 OF 130