STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 17

Metric

MILE MARKER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	~~SQUARE STEEL (mm) kg/m 44 3.4~~	~~50 3.9~~	~~63 5.0~~	~~ANCHOR~~	~~SLLVF~~	TUBULAR ALUMINUM DIA (mm) kg/m 75 1.9	100 2.5	100MD 2.5	TUBULAR STEEL DIA (mm) kg/m FND-ATION	75 11.3	90 13.6	100 16.1	125 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
INT.#1 7.451 RTE 18 LT	NORTH	1	600	300	0.18																													M3-1		E-135
	INTERSTATE 93	1	600	600	0.36																													M1-1		E-135
	←	1	525	375	0.20						1			4.877 X		X		X																M6-1		E-135
7.451 RTE 18 LT	SOUTH	1	600	300	0.18																													M3-3		E136-B
	VERMONT 18	1	600	600	0.36																													M1-5		E-136B
	←	1	525	375	0.20						1			4.877 X		X		X																M6-1		E136-B
7.455 RTE 18 RT	STOP / DO NOT ENTER	1 1	750 750	750 750	0.56 0.56																													R1-1 BACK TO BACK R5-1		E-143 E-143
	ONE WAY / ONE WAY	1 1	900 900	300 300	0.27 0.27						1			4.267 X		X		X																R6-1L BACK TO BACK R6-1R		E-142 E-142
7.473 RTE 18 LT	◆	1	450	450	0.20						1		2.438 X		X			X																OM-1		E-150
7.500 RTE 18 LT	TRUCK ROUTE	1	600	450	0.27																													R14-1		
	SOUTH / WEST	1 1	600 600	300 300	0.18 0.18																													M3-3 M3-4		E136-B E-136A
	VERMONT 18 / 2	1 1	600 600	600 600	0.36 0.36																													M1-5 M1-4		E-136B E-136A
	↑ / ↗	1 1	525 525	375 375	0.20 0.20																											#2		M6-3 M6-2		E136-B E-136A
	SOUTH / NORTH	1 1	600 600	300 300	0.18 0.18																													M3-3 M3-1		E-135 E-135
	INTERSTATE 93 / INTERSTATE 93	1 1	600 600	600 600	0.36 0.36																													M1-1 M1-1		E-135 E-135
	↑ / ↗	1 1	525 525	375 375	0.20 0.20						2												2	117 X								#2		M6-3 M6-2		E-135 E-135
												m 0.0	m ~~2.7~~ 2.44	m ~~13.2~~ 14.03	m 0.0	m 2.7	m 13.2		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg ~~108.5~~	kg 0.0	kg 0.0	kg 0.0								
												16.5												117											
		SHEET TOTALS			m2 6.57	m2 0.00	EA. 0	m2 ~~0.00~~				m ~~15.9~~			m ~~15.9~~					kg 0.0			EA. 2	kg ~~108.5~~				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: WATERFORD
PROJECT NUMBER: HES 093-1(10)

FILE NAME:	tsssWaterford.xls	PLOT DATE:	1/4/2007
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	PTS	CHECKED BY:	DAM
CLD REF. NO.:	97-0211	SHEET	112 OF 130