QUANTITIES

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
1200		1200	SY	COLD PLANING-BIT. PAVEMENT	210.10	30
18,000		18,000	LB	BITUMINOUS CRACK SEALING	417.10	EST.
250		250	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
300		300	HR	FLAGGERS	630.15	EST.
	1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	
1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	
1		1	LS	TRAFFIC CONTROL	641.10	
2		2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
39,750		39,750	LF	6 '' WHITE LINE	646.214	
31,750		31,750	LF	6 '' YELLOW LINE	646.215	
500		500	LF	12 '' WHITE LINE	646.24	
800		800	EA	LINE STRIPING TARGETS	646.76	EST.
18,075		18,075	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST.
95,000		95,000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	
15		15	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SURFACE PREPARATION) (PG 58-34)	900.680	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING-BIT. PAVEMENT
150	SY	BEGIN PROJECT
150	SY	END PROJECT
600	SY	BRIDGE 34-S & BRIDGE 35-S APPROACHES
135	SY	RAMP C INTERCHANGE 5
135	SY	RAMP D INTERCHANGE 5
1170	SY	SUBTOTAL
30	SY	ROUNDING
1200	SY	TOTAL
		PAVER-PLACED SURFACE TREATMENT, TYPE C
94,674	SY	MAINLINE, MM 37.950 - MM 43.953
326	SY	INTERCHANGE 5 RAMP C & RAMP D
95,000	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BROOKFIELD-WILLIAMSTOWN_
PROJECT NUMBER: IM_SURF(3)_____

FILE NAME: p06g168.dgn_____ PLOT DATE: 28-MAY-2010 12:5
PROJECT LEADER: WOOLAVER_____ DRAWN BY: LOCKE_____
DESIGNED BY: LOCKE_____ CHECKED BY: PAVI_MGMT____
p06g168gs.t_____ SHEET 3____ OF 8_____