STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #1

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
I-91 NB MM STA. 45.00 RT 46.00 RT 47.00 RT 48.00 RT 49.00 RT 50.00 RT 51.00 RT 52.00 RT 53.00 RT 54.00 RT 55.00 RT 56.00 RT 57.00 RT		13	12	36	39.00						13			X @12'/EA 13X12 =157'		X																			E-139
I-91 NB MM STA. 50.317 RT	INSTALLED/SUPPLIED WRONG INITIALLY. DID IT 2X	1	45	36	11.25																												OVERLAY SIGN PANEL FOR GUIDE SIGN USE	24	E-136B
		1	36	36	9.00																												OVERLAY SIGN PANEL FOR GUIDE SIGN USE	24	E-136A
		1	36	36	9.00																												OVERLAY SIGN PANEL FOR GUIDE SIGN USE	24	E-136B
I-91 NB MM STA. 50.900 RT		1	144	144		144.00					2																	2		405.9 873#	W8x18			26	
I-91 NB MM STA. 51.050 RT		1	48	48	16.00				1	1 EXIST	1 NEW ~~2~~			USED EXISTING SIGN POST IN PLACE. ADDED 1 NEW 2 X 1@18'		~~X~~																			E-150
I-91 NB MM STA. 51.185 RT	INSTALLED/SUPPLIED WRONG INITIALLY. DID IT 2X	1	45	36	11.25																												OVERLAY SIGN PANEL FOR GUIDE SIGN USE	24	E-136B
		1	36	36	9.00																												OVERLAY SIGN PANEL FOR GUIDE SIGN USE	24	E-136A
		1	36	36	9.00																												OVERLAY SIGN PANEL FOR GUIDE SIGN USE	24	E-136B
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
														186		186																			
	SUBTOTALS SIGN SHEET 1		SF 113.50	SF 144.00	EA.	SF						FT 186			FT 186					LB			EA.	LB				EA. 2	EA.	LB 405.9					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: SPRINGFIELD - WINDSOR
PROJECT NUMBER: IM 091-1(55)

FILE NAME: 06A194.dgn
PROJECT LEADER: LFW
DESIGNED BY: LFW
PLOT FILE: 06A196tssl.i

PLOT DATE: 28-OCT-2011 14:01
DRAWN BY: LFW
CHECKED BY: LFW
SHEET 20 OF 36