STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
EXIT 8 RAMP D ON RAMP 1+00 RT	TURN SIGNAL REQUIRED BEFORE CHANGING LANES	1	36	36	9.00						2			X		X						2 EA 1@14' 1@14.75' 28.75 @7.6#/FT 218.5#											THE SURFACE AREA OF THE NEW SIGNS REQUIRED TUBULAR STEEL W7 FOUNDATIONS		E-142
	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	36	36	9.00																													E-142
EXIT 8 RAMP D ON RAMP 9+15 RT		1	30	30	6.25						1			X 1@14'		X																		E-143
NB EXIT 8 OFF RAMP GORE	EXISTING 9 BUTTON SIGN (FOUND ON GROUND)										1			1@8' X																				
	SUBTOTALS THIS SHEET				24.25	--								45		45						-- 2	--											
	SUBTOTALS SIGN SHT. 1				113.50	144.00								186		186						--	--											
	SUBTOTALS SIGN SHT. 2				87.50	144.00								60		60						2	228											
	SUBTOTALS SIGN SHT. 3				67.00 292.255	--								150		150						--	--											
	ROUNDING				7.75	--								19		19						--	22											
												FT	FT	FT 460	FT	FT 460	FT	EA	LB	LB	LB		LB 250	LB	LB	LB								
	TOTALS				SF 300.00	SF 288.00	EA.	SF						FT 460		FT 460				LB		EA. 2-4	LB 250				EA. 4	EA.	LB 825					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: SPRINGFIELD - WINDSOR
PROJECT NUMBER: IM 091-1(55)

FILE NAME: 06AI94.dgn
PROJECT LEADER: LFW
DESIGNED BY: LFW
PLOT FILE: 06AI96tss4.i
PLOT DATE: 28-OCT-2011 14:02
DRAWN BY: LFW
CHECKED BY: LFW
SHEET 23 OF 36