QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

			FULL E&C	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						100	100	CY	COMMON EXCAVATION	203.15	EST.
						525	525	CY	EARTH BORROW	203.30	-
						7600	7600	LF	SHOULDER BERM REMOVAL	203.40	43
						1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
									BEGIN OPTION AA		
						210000	210000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	2234.57
									(CONTRACTOR RETAINS ALL EXCESS GRINDINGS)		
						210000	210000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	2234.57
									(AGENCY RETAINS REQUESTED EXCESS GRINDINGS)		
									END OPTION AA		
						94000	94000	LF	MILLED RUMBLE STRIPS	213.10	1080
						3650	3650	TON	AGGREGATE SHOULDERS, RAP	402.13	56
						1000	1000	CWT	EMULSIFIED ASPHALT	404.65	27.08
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
									BEGIN OPTION BB		
						29000	29000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	407.68
									(0% RAP CONTENT)		
						29000	29000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	407.68
									(0% < RAP CONTENT < 15.0%)		
						29000	29000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	407.68
									(15.0% <= RAP CONTENT < 25.0%)		
						29000	29000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	407.68
									(25.0% <= RAP CONTENT <= 50.0%)		
									END OPTION BB		
						1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
						1	1	LU	MAT. DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
						1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
						1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
					220		220	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	5
					100		100	CF	RAPID SETTING CONC. REPAIR MAT. W/ COARSE AGG.	580.20	EST.
						7	7	EA	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-
						11	11	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
						11	11	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
						11	11	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-
						400	400	HR	POWER GRADER RENTAL	608.15	EST.
						400	400	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
199162.22	SY	MAINLINE - NB TRAVEL LANES
4598.21	SY	INTERCHANGE 17
4005.00	SY	INTERCHANGE 18
2234.57	SY	ROUNDING
210000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONC. PAVEMENT
		TYPE IVS (WEARING SURFACE)
21982.72	TON	MAINLINE - NB TRAVEL LANES
383.18	TON	INTERCHANGE 17
333.97	TON	INTERCHANGE 18
201.92	TON	BRIDGES (TYPE IVS)
5690.52	TON	LEVELING (TYPE IVS)
6000	TON	10' SHOULDER, 2" COLD PLANED DEPTH
407.68	TON	ROUNDING
~~29000~~	TON	TOTAL
35000		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: COLCHESTER - GEORGIA
PROJECT NUMBER: IM 089-3(64)

FILE NAME: p06a196.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p06a196qsl.i

PLOT DATE: 04-OCT-2011 16:52
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 6 OF 23