

STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET 2

604.412
604.415

BEGIN MILEMARKER	END MILEMARKER	POS.	203.30	203.40	WASTE DITCHING MATERIAL	402.13	604.40	604.418	613.10	616.305	616.41	616.47	619.17	620.12	620.21	621.20	621.50	621.60	621.76	621.77	621.80	676.10					676.12	REMARKS
			EARTH BORROW	SHOULDER BERM REMOVAL		AGG. SHOULDR. RAP	CHANGE ELEV. OF D. I.	REHAB. D. I. CLASS I, II OR III	STONE FILL, TYPE I	BITUM. CONC. CURB, TYPE A	REMOVAL EXIST CURB	BITUM. CONC. GUTTERS	YIELDING MARKER POSTS	CHAIN-LINK FENCE 6 FEET	BRACE ASSEMBLY	STEEL BEAM G. R. GALV.	MANUF. TERMINAL SECTION FLARED	ANCHOR FOR S. B. RAIL	REPLACE G. R. POST	REPLACE G. R. BEAM	REMOVE & DISP. OF G. R.	TYPE I GUARD RAIL ENDS	TYPE I RAMPS	TYPE II	TYPE III	TYPE I WITH PLAQUE	TYPE I WITHOUT PLAQUE	
			CY	FT	CY	TON	EACH	EACH	CY	FT	FT	TON	EACH	FT	EACH	FT	EACH	EACH	EA	EA	FT	EACH	EACH	EACH	EACH	EACH	EACH	
5527+00	5527+40	RT							5					50	3													ESTIMATED QUANTITY TO REPAIR ERODED AREA
5525+02	5527+51	RT	25	169		5											1		4	4	37.5	2						INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 5525+02
5562+14		RT							5																			ESTIMATED QUANTITY TO REPAIR ERODED AREA
5533+81	5539+07	RT	25	106		5											1		4	4	37.5	2						INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 5533+81
5553+26	5578+10	RT	25	309		5											1		6	16	37.5	2						INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 5553+26
5553+55	5565+93	LT	25	1050		5											1		4	6	37.5	2						INSTALL NEW MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 5553+55
5573+14	5577+88	LT	25	349		5											1		4	6	37.5	1						INSTALL MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 5573+14
BRIDGE #84 N																												
5579+81	5580+63	LT		66															1	3		1						REPLACE BEAMS AND POSTS AS NECESSARY
5579+95	5585+99	RT		105															16	16		2						REPLACE BEAMS AND POSTS AS NECESSARY
5620+75	5626+04	LT		423															16	8								RETAIN EXISTING STEEL BEAM GUARDRAIL
5621+87	5625+79	RT	25	284		5											1		2	10	37.5	2						INSTALL MANUFACTURED TERMINAL SECTION (FLARED) AT STA. 5621+87
EXIT 17 RAMP C																												
1+02	2+16	RT														139.5		1			137.5							INSTALL ANCHOR AT STA. 2+16; REMOVE TEXAS TWIST
EXIT 18 RAMP A																												
10+48		LT						1																				
SUBTOTAL THIS SHEET			150	2861	-	30	-	1	10	-	-	-	-	50	3	139.5	6	1	57	73	362.5	14	-	-	-	-	-	
SUBTOTAL SHEET 8			375	4696	519	3564	7	32	37	367	367	2.60	50	-	-	114.5	15	1	79	101	677	30	52	31	16	175	90	408
ROUNDING			-	43	-	56	-	-	-	8	8	.40	-	-	-	8.5	-	-	-	-	0.5	-	-	-	-	-	-	
GRAND TOTAL			525	7600	519	3650	7	33	47	375	375	3.00	50	50	3	262.5	21	2	136	174	1040	44	52	31	16	175	90	408

ITEM DETAIL SUMMARY SHEET #2	PROJECT NAME: COLCHESTER - GEORGIA
	PROJECT NUMBER: IM 089-3(64)
	FILE NAME: p06a196.dgn
	PLOT DATE: 04-OCT-2011 16:52
	PROJECT LEADER: CDL
	DRAWN BY: SJL
	DESIGNED BY: SJL
	CHECKED BY: EPD
	PLOT FILE: p06a196idss2.i
	SHEET 10 OF 23