



**RAMP RADII INFORMATION**

RAMP	RADII, FT	DESCRIPTION
C	450	STA. 4+65 TO STA. 7+40
	275	STA. 7+40 TO STA. 9+03
	560	STA. 12+61 TO STA. 17+00

REMOVAL=3+4+2+3+2=14

- 616.47 BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS
- RAMP C  
STA. 5+16 LT
- 621.20 STEEL BEAM GUARDRAIL, GALVANIZED
- RAMP C  
STA. 1+02 RT TO STA. 2+16 RT
- 621.60 ANCHOR FOR STEEL BEAM RAIL
- RAMP C  
STA. 2+16 RT
- 621.80 REMOVAL AND DISPOSAL OF GUARDRAIL
- RAMP C  
STA. 1+02 RT TO STA. 2+16 RT
- 646.426 DURABLE 6 INCH WHITE LINE, RECESSED
- RAMP C  
STA. 1+17 TO STA. 17+13 (SOLID RT)
- MAINLINE  
STA. 5179+75 TO STA. 5187+30 (SOLID RT)  
STA. 5179+75 TO STA. 5182+00 (DASHED RT)
- 646.436 DURABLE 6 INCH YELLOW LINE, RECESSED
- RAMP C  
STA. 1+17 TO STA. 15+45 (SOLID LT)
- 646.466 DURABLE 12 INCH WHITE LINE, RECESSED
- MAINLINE  
STA. 5177+98 TO STA. 5179+72 (GORE MARKING)  
EXIT 17 RAMP C  
STA. 15+40 - STA. 16+53 LT (GORE MARKING)
- 646.622 TEMPORARY 6 INCH WHITE LINE, PAINT
- RAMP C  
STA. 1+17 TO STA. 17+13 (SOLID RT)
- MAINLINE  
STA. 5179+75 TO STA. 5187+30 (SOLID RT)  
STA. 5179+75 TO STA. 5182+15 (DASHED RT)
- 646.632 TEMPORARY 6 INCH YELLOW LINE, PAINT
- RAMP C  
STA. 1+17 TO STA. 15+45 (SOLID LT)
- 646.662 TEMPORARY 12 INCH WHITE LINE, PAINT
- MAINLINE  
STA. 5177+98 TO STA. 5179+72 (GORE MARKING)  
EXIT 17 RAMP C  
STA. 15+40 - STA. 16+53 LT (GORE MARKING)
- 675.50 REMOVING SIGNS  
AS SHOWN - 7

**LEGEND**

- N = NEW
- R = REMOVE
- B-B = BACK TO BACK
- RET = RETAIN

**RAMP DETAIL SHEET INTERCHANGE #17 RAMP C**

PROJECT NAME: COLCHESTER - GEORGIA	PLOT DATE: 04-OCT-2011 16:52
PROJECT NUMBER: IM 089-3(64)	DRAWN BY: RHB/SJL
FILE NAME: p06a196.dgn	DESIGNED BY: SJL
PROJECT LEADER: CDL	CHECKED BY: EPD
PLOT FILE: p06a196rdsil7c.i	SHEET 13 OF 23

NOT TO SCALE