STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16 (~~2.16~~)	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) lb/ft FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA. 5209+57 RT	SPEED LIMIT 65 / MINIMUM 40	1 1	48 48	60 48	20.00 16.00						2					12 GA							2 X	X									R2-1 VR-141		E-142
STA. 5356+09 RT	BRIDGE ICES BEFORE ROAD	1	48	48	16.00						2					16 X 16			X														W8-13		E-150
STA. 5362+60 RT	LAMOILLE RIVER	1	36	24	6.00						2					14 X 14			X														I-3	I7	
STA. 5362+98 LT&RT		1 1	12 12	36 36	3.00 3.00						2					10 X 10			X														OM-3L OM-3R		E-107
STA. 5547+25 RT	ENTERING TOWN OF GEORGIA FRANKLIN CO	1	48	42	14.00						2					14 X 14			X														I-2TC	I7	
STA. 5578+02 LT		1	12	36	3.00						1					10 X			X														OM-3R		E-107
STA. 5578+24 RT		1	12	36	3.00						1					10 X			X														OM-3L		E-107
STA. 5618+56 RT		1	48	48	16.00						2					16 X 16			X														W4-1		E-150
STA. 5621+30 LT	ONE WAY	1	54	18	6.75						2					12 X			X														R6-1R		E-142
STA. 10+12 LT EXIT 18 RAMP A	0070 0608 1272	1 1 1	24 18 6	30 18 10	5.00 2.25 0.42						1					12 X			X														R4-7 0MI-1		E-144 E-150 E-138
STA. 10+14 RT EXIT 18 RAMP A	NORTH INTERSTATE 89	1 1 1	24 24 21	12 24 15	2.00 4.00 2.19						1					16 X			X														M3-1 MI-1 M6-1		E-135
STA. 11+43 RT EXIT 18 RAMP A	TURN SIGNAL REQUIRED BEFORE CHANGING LANES / PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1 1	36 36	36 36	9.00 9.00						2					16 16 X			X														VR-002 VR-046		E-142
												FT	FT	FT	FT	FT ~~285~~ 232	FT		EA	LB	LB	LB		LB 228	LB	LB	LB								
TOTALS		SF 140.61	SF	EA.	SF		FT		FT 285			LB			EA. 1	LB 228				EA.	EA.	LB														

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE VTRANS STANDARD SHEETS AND "SIGN POST DESIGN GUIDELINE".

TRAFFIC SIGN SUMMARY SHEET 2

PROJECT NAME: COLCHESTER - GEORGIA
PROJECT NUMBER: IM 089-3(64)

FILE NAME: p06a196.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p06a196tss2.i

PLOT DATE: 04-OCT-2011 16:52
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 17 OF 23