

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES					TOTALS		DESCRIPTIONS			
ROADWAY	EMPLOYEE TRAINEESHIP	BRIDGE	EROSION CONTROL	FULL C. E. ITEMS	GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND	
55					55	CY	COMMON EXCAVATION	203.15	1.9	
960					960	CY	EARTH BORROW	203.30	10	
24200					24200	LF	SHOULDER BERM REMOVAL	203.40	101	
1					1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	
361500					361500	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	215	
129000					129000	LF	MILLED RUMBLE STRIPS	213.10	349	
4					4	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	0.3	
6					6	TON	SUBBASE, RAP	301.40	0.1	
130					130	TON	AGGREGATE SHOULDERS, RAP	402.13	5	
1500					1500	CWT	EMULSIFIED ASPHALT	404.65	6.4	
1					1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-	
42250					42250	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	152	
1					1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-	
1					1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-	
1					1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-	
1					1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-	
		175			175	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	1	
		100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.	
39					39	EA	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	EST.	
35					35	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.	
34					34	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	EST.	
34					34	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	EST.	
445					445	HR	POWER GRADER RENTAL	608.15	EST.	
445					445	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.	
265					265	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.	
445					445	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.	
445					445	HR	TRUCK RENTAL	608.37	EST.	
445					445	HR	LOADER RENTAL, TYPE I	608.40	EST.	
			110		110	CY	STONE FILL, TYPE I	613.10	3.7	
			50		50	CY	STONE FILL, TYPE II	613.11	EST.	
1300					1300	LF	TREATED TIMBER CURB	616.35	22	
35					35	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	2.1	
25					25	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	2.8	
26					26	SF	DETECTABLE WARNING SURFACE	618.30	2	
325					325	EA	YIELDING MARKER POSTS	619.17	6	
310					310	LF	SNOW BARRIER, GALVANIZED	620.75	9	
6900					6900	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	40.5	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
162725	SY	NORTHBOUND MAINLINE
2203	SY	NORTHBOUND BRIDGES
148130	SY	SOUTHBOUND MAINLINE
1294	SY	SOUTHBOUND BRIDGES
14789	SY	INTERCHANGE NO. 27 RAMPS
14765	SY	INTERCHANGE NO. 28 RAMPS
8160	SY	INTERCHANGE NO. 29 RAMPS
8452	SY	WELCOME CENTER
767	SY	U-TURNS
215	SY	ROUNDING
361500	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
14238	TON	NORTHBOUND MAINLINE WEARING COURSE
162	TON	NORTHBOUND BRIDGES WEARING COURSE
12961	TON	SOUTHBOUND MAINLINE WEARING COURSE
95	TON	SOUTHBOUND BRIDGES WEARING COURSE
1294	TON	INTERCHANGE NO. 27 RAMPS WEARING COURSE
1292	TON	INTERCHANGE NO. 28 RAMPS WEARING COURSE
714	TON	INTERCHANGE NO. 29 RAMPS WEARING COURSE
739	TON	WELCOME CENTER WEARING COURSE
171	TON	U-TURNS WEARING COURSE
10432	TON	LEVELING
152	TON	ROUNDING
42250	TON	TOTAL
		STONE FILL, TYPE I
60	CY	DITCH CLEANING
46.3	CY	SLOPE EROSION REPAIR
3.7	CY	ROUNDING
110	CY	TOTAL
		GEOTEXTILE UNDER STONE FILL
280	SY	DITCH CLEANING
496	SY	SLOPE EROSION REPAIR
24	SY	ROUNDING
800	SY	TOTAL

PROJECT NAME: DERBY	PLOT DATE: 07-SEP-2011 10:21
PROJECT NUMBER: IM 091-3(46)	DRAWN BY: STANTEC
FILE NAME: p06a200.dgn	CHECKED BY: JLL
DESIGNED BY: STANTEC	SHEET 6 OF 63
IPARM FILE: p06a200qs01.i	