

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	TRAINING	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITY	UNIT	ITEMS
							1750				1750		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77	EST.			
							1650				1650		LF	ADJUST HEIGHT OF GUARDRAIL	621.79	EST.			
							7400				7400		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	40			
							3000				3000		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							1800				1800		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
								520			520		HR	EMPLOYEE TRAINEESHIP	634.10	-			
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1				1		LS	TRAFFIC CONTROL	641.10	-			
							12				12		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
														BEGIN OPTION AA					
							143600				143600		LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426	157			
							143600				143600		LF	DURABLE 6 INCH WHITE LINE, RECESSED THERMOPLASTIC	646.428	157			
							143600				143600		LF	DURABLE 6 INCH WHITE LINE, RECESSED EPOXY PAINT	646.429	157			
														END OPTION AA					
														BEGIN OPTION BB					
							116600				116600		LF	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	646.436	163			
							116600				116600		LF	DURABLE 6 INCH YELLOW LINE, RECESSED THERMOPLASTIC	646.438	163			
							116600				116600		LF	DURABLE 6 INCH YELLOW LINE, RECESSED EPOXY PAINT	646.439	163			
														END OPTION BB					
														BEGIN OPTION CC					
							10500				10500		LF	DURABLE 12 INCH WHITE LINE, RECESSED POLYUREA	646.466	56			
							10500				10500		LF	DURABLE 12 INCH WHITE LINE, RECESSED EPOXY PAINT	646.469	56			
														END OPTION CC					
														BEGIN OPTION DD					
							30				30		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	9			
							30				30		LF	DURABLE 24 INCH STOP BAR, EPOXY PAINT	646.483	9			
														END OPTION DD					
														BEGIN OPTION EE					
							95				95		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-			
							95				95		EACH	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-			
														END OPTION EE					
							287200				287200		LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	313			
							233200				233200		LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	326			
							21000				21000		LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	112			
							60				60		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	18			
							190				190		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
							8700				8700		EACH	LINE STRIPING TARGETS	646.76	EST.			

PROJECT NAME: HARTLAND-NORWICH  
PROJECT NUMBER: IM 091-1(59)  
FILE NAME: /pave/06a202/p06a202.dgn PLOT DATE: 19-JUN-2013 09:24  
PROJECT LEADER: PTS DRAWN BY: WWG  
DESIGNED BY: NULL CHECKED BY: PTS  
IPARM FILE NAME: 06A202\_18 SHEET 18 OF 60