

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE NO. 1 (MM 117.72)	BRIDGE NO. 2 (MM 117.96)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						279				279		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	3			
						152				152		CY	EARTH BORROW	203.30	2			
								70	50	120		CY	STRUCTURE EXCAVATION	204.25	5			
								60	40	100		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	12			
								14	14	28		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	2			
								2000	1970	3970		LB	REINFORCING STEEL	507.15	57			
								5	5	10		GAL	WATER REPELLENT, SILANE	514.10				
						5				5		CY	REMOVAL OF CONCRETE OR MASONRY	529.25	1			
						18				18		HR	BULLDOZER RENTAL, TYPE I	608.10				
						4				4		HR	POWER BROOM RENTAL, TYPE I	608.30				
						84				84		CY	STONE FILL, TYPE II	613.11	1			
						138				138		CY	STONE FILL, TYPE III	613.12	2			
						80				80		LF	CHAIN-LINK FENCE, 6 FEET	620.12	9			
						80				80		LF	REMOVAL OF EXISTING FENCE	620.55	9			
						80				80		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
						1				1		LS	TRAFFIC CONTROL	641.10				
						2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						418				418		SY	GEOTEXTILE UNDER STONE FILL	649.31	5			
							105			105		SY	GEOTEXTILE FOR SILT FENCE	649.51	2			
						2				2		LB	SEED	651.15	1			
						10				10		LB	FERTILIZER	651.18	1			
						1				1		TON	AGRICULTURAL LIMESTONE	651.20	0.1			
						1				1		TON	HAYMULCH	651.25	0.1			
						6				6		CY	TOPSOL	651.35	1			
							1641			1641		LF	PROJECT DEMARCATION FENCE	653.55	17			
						2				2		EACH	REMOVING SIGNS	675.50				
						2				2		EACH	ERECTING SALVAGED SIGNS	675.60				
						2				2		EACH	SETTING SALVAGED POSTS	675.61				
						50				50		CY	SPECIAL PROVISION (CONTROLLED DENSITY (FLOWABLE) FILL)	900.608				
						22				22		EACH	SPECIAL PROVISION (TEST BORINGS)	900.620				
									325	325		LF	SPECIAL PROVISION (CURED-IN-PLACE PIPE LINER) (54")	900.640	20			
								453		453		LF	SPECIAL PROVISION (CURED-IN-PLACE PIPE LINER) (60")	900.640	20			
								0.6	0.4	1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)	900.645				
								0.5	0.5	1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645				

PROJECT NAME: **BARNET**
PROJECT NUMBER: **IM SCR(2)**
FILE NAME: d07a102fm.dgn PLOT DATE: 02/22/2008
PROJECT MANAGER: K. UPMAL DRAWN BY: J. DEVLIN
DESIGNED BY: J. DEVLIN CHECKED BY: K. UPMAL
QUANTITY SHEET #1 SHEET 2 OF 20