

TRAFFIC CONTROL NOTES

① TEMPORARY LANE AND/OR SHOULDER CLOSURES SHALL ONLY BE USED TO TRANSPORT MATERIAL AND EQUIPMENT TO DESIGNATED LOCATIONS ASSOCIATED WITH THE PROPOSED CULVERT INLET/OUTLET.

② TEMPORARY LANE AND/OR SHOULDER CLOSURES SHALL ONLY BE ALLOWED BETWEEN THE HOURS OF 7:00 PM AND 7:00 AM OR DURING A SET TIME AND DURATION APPROVED BY THE RESIDENT ENGINEER. REFER TO PROJECT SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION.

③ WHERE TEMPORARY TRAFFIC BARRIER IS USED, BARRIER ENDS FACING ONCOMING TRAFFIC SHALL BE TAPERED BEYOND THE CLEAR ZONE, OR PROTECTED WITH AN APPROVED END TREATMENT.

④ NON -CRASHWORTHY FEATURES RESULTING FROM CONSTRUCTION ACTIVITIES THAT ARE LOCATED WITHIN THE CLEAR ZONE SHALL BE PROPERLY PROTECTED. ALL TEMPORARY DEVICES SHALL BE NCHRP REPORT 350 COMPLIANT AND SHALL BE FURNISHED IN ACCORDANCE WITH SECTION 621.

⑤ TRAFFIC CONTROL WARNING SIGNS SHALL BE PROVIDED ON EACH APPROACH PER THE MUTCD. ADDITIONAL PROJECT CONSTRUCTION SIGNS SHALL BE INSTALLED AS REQUIRED BY THE RESIDENT ENGINEER PER THE MUTCD. PAYMENT FOR THESE SIGNS, THE REFLECTORIZED PLASTIC DRUMS, ETC., SHALL BE MADE UNDER CONTRACT ITEM NO. 641.10.

⑥ TEMPORARY LANE AND/OR SHOULDER CLOSURES SHALL BE USED WHEN REMOVING EQUIPMENT AND DEBRIS ASSOCIATED WITH CONSTRUCTION ACTIVITIES.

⑦ PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT TO THE ROADWAY, TRAFFIC, AND SAFETY ENGINEER SITE-SPECIFIC TRAFFIC CONTROL PLANS. THE ROADWAY, TRAFFIC AND SAFETY ENGINEER SHALL APPROVE THESE PLANS PRIOR TO THE START OF CONSTRUCTION ACTIVITIES AS STATED IN SECTION 641.02 OF VERMONT AGENCY OF TRANSPORTATION STANDARD SPECIFICATIONS.

PROJECT NAME: SOUTH BURLINGTON
PROJECT NUMBER: IM SCRP(3)

FILE NAME: d07a104_frm.dgn PLOT DATE: 13-JAN-2010
PROJECT LEADER: K. UPMAL DRAWN BY: B. KIPP
DESIGNED BY: B. KIPP/B. McADAMS CHECKED BY: B. KIPP
TRAFFIC CONTROL NOTES SHEET 49 OF 69