

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES						
										ROADWAY	EROSION CONTROL	BRIDGE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	EST.			
										32			32		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	1			
										50			50		CY	EARTH BORROW	203.30	2			
												104	104		CY	STRUCTURE EXCAVATION	204.25	2			
												72	72		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	1			
												29	29		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	1			
												3130	3130		LB	REINFORCING STEEL	507.15	52			
												15	15		GAL	WATER REPELLENT, SILANE	514.10	EST.			
										4			4		CY	REMOVAL OF CONCRETE OR MASONRY	528.25	1			
										30			30		LF	8 INCH UNDERDRAIN CARRIER PIPE	605.20	EST.			
										32			32		CY	STONE FILL, TYPE II	613.12	1			
										20			20		CY	STONE FILL, TYPE IV	613.13	EST.			
										37.5			37.5		LF	REMOVE AND RESET GUARDRAIL	621.75	EST.			
										60			60		LF	TEMPORARY TRAFFIC BARRIER	621.90	EST.			
										90			90		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95	EST.			
										40			40		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
										1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	EST.			
										1			1		LS	TRAFFIC CONTROL	641.10	EST.			
										48			48		SY	GEOTEXTILE UNDER STONE FILL	649.31	1			
											28		28		SY	GEOTEXTILE FOR SILT FENCE	649.51	1			
										1			1		LB	SEED	651.15	1			
										5			5		LB	FERTILIZER	651.18	1			
										0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
										0.5			0.5		TON	HAYMULCH	651.25	EST.			
										3			3		CY	TOPSOIL	651.35	EST.			
											1		1		LS	EPSC PLAN	652.10	EST.			
											8		8		HR	MONITORING EPSC PLAN	652.20	EST.			
											1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	EST.			
											532		532		LF	PROJECT DEMARCATION FENCE	653.55	5			
										25			25		CY	SPECIAL PROVISION (CONTROLLED DENSITY/FLOWABLE) FILL	900.608	EST.			
												142	142	136	LF	SPECIAL PROVISION (CURED-IN-PLACE PIPE LINER) (88')	900.640	1			
										180			180		LF	SPECIAL PROVISION (TEST BORINGS)	900.640	10			
												1	1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, CULVERT)	900.645	EST.			
												1	1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645	EST.			

PROJECT NAME: RUGGINSHAM  
 PROJECT NUMBER: 100 0000 (S)  
 PROJECT MANAGER: B. SPYRAL  
 DESIGNED BY: T. GUAZZONI  
 CHECKED BY: B. KIPP  
 QUANTITY SHEET BY: [Blank]  
 SHEET 7 OF 17